

CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

SEPTEMBER 1961



VOL. LVI. NO. 9

FIFTY-SIXTH YEAR OF PUBLICATION

PRICE 3s.

ANNUAL SUBSCRIPTION 14s. POST FREE. \$3.90 in Canada and U.S.A.

LEADING CONTENTS

	PAGE
Earthquake-resistant Construction	297
The Analysis of Three-bay Frames by the Plastic-hinge Method	
By K. Poologasundram, Ph.D., A.M.I.C.E.	301
Concrete Construction at Trawsfynydd Nuclear Power Station	307
Shearing Resistance of Beams by the Load-factor Method	
By C. Erdel, B.Sc. Eng. (Hungary)	315
A Practical Comprehensive Method of Designing Reinforced Concrete Sections.—IV	
By J. Rygol, B.Sc.(Eng.)	323
Concrete Avalanche Sheds	325
Standard Prestressed Beams	327
British Standard Notation for Concrete Structures	328

No. 646

ISSUED MONTHLY

Registered for
Canadian Magazine Post

BOOKS ON CONCRETE

For Catalogue of "Concrete Series" books on concrete and allied subjects, send a postcard to:

CONCRETE PUBLICATIONS LTD., 14 DARTMOUTH ST., LONDON, S.W.1.

INDEX OF ADVERTISERS

	Page		Page
A.B. MOULD & CONSTRUCTION CO. LTD.	ix	LECA (Great Britain) LTD.	—
A.C.E. MACHINERY LTD.	ixv	LEDS OIL & GREASE CO. LTD.	iii
ARLSON & CO. (ENGINEERS) LTD.	ixvi	LENSCARTS LTD.	ixi
ALLAN, E. F., & CO. LTD.	ixxi	LEVINTON (INDUSTRIAL) LTD.	viii
ALLIED BUILDING COMMODITIES	—	LILLINGTON, GEORGE & CO. LTD.	ixviii
AMGLAN BUILDING PRODUCTS LTD.	—	LIND, PETER, & CO. LTD.	v
ATLAS STONE CO. LTD.	ixiii	LOWDEN, GEORGE, & SON LTD.	—
BARVIS, A. & C. LTD.	—	McCALL & CO. (SHEFFIELD) LTD.	ixii
BERRY'S ENGINEERING CO.	ixviii	McCALLS MACALLOY LTD.	—
BOULDER EQUIPMENT LTD.	—	McKINNEY FOUNDATIONS LTD.	ixxiii
BOYER, WM., & SONS LTD.	i	MACHINERY (CONTINENTAL) LTD.	—
BRADTHWAITE & CO., ENGINEERS LTD.	ixiv	MASONITE LTD.	—
B.R.C. ENGINEERING CO. LTD.	ixxxviii	MASSEY, A. H., LTD.	viii
BRETT, ROBERT, & SONS LTD.	—	MAY & BUTCHER LTD.	ixxii
BRITISH OXYGEN CO. LTD.	—	MILBURN FLOORS LTD.	ixix
BRITISH STEEL PILING CO. LTD.	—	MILLARD'S MACHINERY CO. LTD.	ixxvi
BUILDING & CONSTRUCTION CO. LTD.	—	MILLS SCAFFOLD CO. LTD.	—
BYRD, A. A., & CO. LTD.	ixxiii	MODULAR CONCRETE CO. LTD.	ixxiv
CABLE COVERS LTD.	ixxi	MONK, A., & CO. LTD.	ixxxv
CALADONIAN MECHANICAL HANDLING CO. LTD.	viii	MULCASTER, WM., & CO. (CONTRACTORS) LTD.	ix
CAPLIN ENGINEERING CO. LTD.	ixii	MYERS, FRED, LTD.	viii
CASTLEHILL SAND & GRAVEL CO. LTD.	—	OMNIA CONSTRUCTIONS LTD.	—
CEMENT MARKETING CO. LTD.	ixxiii	OVERSEA COMMODITIES (SOC.) LTD.	ix
CEMENT & STEEL LTD.	xii	P.S.C. EQUIPMENT LTD.	ixvi, ixvii
CHESTNATH, ALEX. J., LTD.	ixxxviii	P.Z. PRESTRESSING CO. LTD.	xiv
CHEMICAL BUILDING PRODUCTS LTD.	ixxi	PASLEY & TRICKEY LTD.	—
CHRISTIAN & NIELSEN LTD.	—	PENNSHIP LTD.	iv
CORRY, GEORGE, SONS & CO. LTD.	—	PITMAN, SIR ISAAC, & SONS LTD.	—
COLCRETE LTD.	ixvii	PORTABLO LTD.	ixxii
CONCRETE PILING LTD.	—	POWELL DUFFRYN TIMBER INDUSTRIES LTD.	—
CONCRETE PROOFING CO. LTD.	ixii	PRESTRESS SALES LTD.	—
CONCRETE PUMP CO. LTD.	ixxv	PRINT, B., & SONS LTD.	ix
CONVEYERS & CO. LTD.	iii	PUMPCRET HIRE CO. LTD.	xiv
COTMAN CONCRETE CO. LTD.	—	RANALAH STEEL MOULDS LTD.	ixx
COULTER, J. E., LTD.	viii	ROVER CAR CO. LTD.	—
COWLES, WM., & SONS LTD.	—	RUSH & TOMPKINS—PAULING GROUP	ixxxviii
CROYDON REINFORCED FIBREGlass CO.	—	RVLAND BROTHERS LTD.	ixxi
D.A. MODELS LTD.	ixiv	SEALOCRETE PRODUCTS LTD.	ixvi
DANDRIDGE, J. & A., LTD.	—	SHARP JONES & CO. LTD.	—
DAVIDSON'S PAPER SALES LTD.	ix	SIMPLEX CONCRETE PILLS LTD.	ixxxvii
DE JONG	ixxix	SOMERSET WIRE CO. LTD.	ixxi
DICKENS, STUART B., LTD.	ixi	SOMERSET WIRE CO. LTD.	ixix
DORMAN LOWE & CO. LTD.	—	STELING LTD.	ixxy
DOUGLAS, ROBERT M. (CONTRACTORS) LTD.	—	STENT PRECAST CONCRETE LTD.	i
DURATURE & WIRE LTD.	ixviii	STIC B PAINT SALES LTD.	ixxiv
ENGINEERING DESIGN & CONSTRUCTION LTD.	ixxvi	STONE COURT BALLAST CO. LTD.	ixxxviii
ENYTON BROS.	vi	STORER, WM. T., & CO. LTD.	xi
EXPANITE LTD.	ixx	STRESSING DEVELOPMENTS LTD.	ixxiii
FARR, A. E., LTD.	—	STUART'S GRANULITHIC CO. LTD.	ixxi
FLEXIBLE DRIVE & TOOL CO. LTD.	ixxxviii	SUMEX & DOREING BRICK CO. LTD.	—
FONDEBLE, SOC. AN., INC.	ix	TARMAC LTD.	—
FORD MOTOR CO. LTD.	ixvii	TECHNICAL PAINT SERVICES	ixi
FRANKFELT LTD.	xv	TENTON BAR CO. LTD.	—
G.K.N. REINFORCEMENTS LTD.	ixxi	THAMES PLYWOOD MANUFACTURERS LTD.	xvi
GLESSON, M. J. (CONTRACTORS) LTD.	—	THELAN & CO. LTD.	—
GOODS ENGINEERING LTD.	—	T.P. POLYPLASTIC CONVERTERS LTD.	—
GUNITE CONSTRUCTION CO. LTD.	ixvi	TREST GRAVELS LTD.	ixxxv
HALL & CO. LTD.	—	TRITON ENGINEERING CO. (SALES) LTD.	xviii
HEAD WEIGHTON TRENDLE LTD.	ixxiii	TRUCK-MIX (MIDLANDS) LTD.	—
HILTON GRAVEL LTD.	—	TUNNEL PORTLAND CEMENT CO. LTD.	ixxxvii
HOLMERSH PILES LTD.	—	UNISTRUT DIVISION OF SANKEY-SHELDON LTD.	—
HOLT & CO. LTD.	—	VOLLMANN, O. A.	i
HUNTLEY & SPARKS LTD.	—	WALKER WRIGHT & CO. LTD.	ixii
IDRAL CASEMENTS (READING) LTD.	—	WELBEC TRADING CO. LTD.	—
IMPERIAL CHEMICAL INDUSTRIES LTD.	—	WELLSMAN BROS. LTD.	—
JOHNSON, RICHARD, & NEPHEW LTD.	—	WESTWOOD, JOSEPH, & CO. LTD.	ixxvi
JONES, T. C., & CO. LTD.	xii	WHITECROSS WIRE CO. LTD.	—
KELSER LTD.	ix	WHITTENED IRON & STEEL CO. LTD.	x, xi
KERRIER-GREENWOOD & CO. LTD.	ixv	WHITLEY MORAN & CO. LTD.	ixvi
KIRK, J. L., & CO. LTD.	—	WILSON, ROY, DICKSON LTD.	iii
KING, J. A., & CO. LTD.	ixvi	WINGET LTD.	ix
LAFARGE ALUMINOUS CEMENT CO. LTD.	ix, ixxx	WOLF ELECTRIC TOOLS LTD.	ixxxix
LAWLER AYRES & CO. LTD.	ixxxiv	YORKSHIRE HERMESIQUE CONTRACTING CO. LTD.	vii
LAW & SON (STAINES) LTD.	—		

LYE

SULPHITE

IN LIQUID FORM

**an important additive for
concrete · grout · and most
forms of ground treatment**

Liquid Sulphite Lye is an effective cement expander, whereby cement shrinkage is obviated, leaving the concrete free from shrinkage cracks. For mass concrete it avoids the deleterious effects of thermal contraction and shrinkage. It is also invaluable for grouting work, and for prestressing cable ducts it ensures that when the grout is set it always completely fills the cable duct and other apertures. Its qualities for ground treatment and tunnelling work have also been proved on important contracts.

Liquid Sulphite Lye is the most effective and economical material for producing air-entrained and colloidal concrete, and will satisfy the most exacting requirements for this class of work.

Sulphite Lye is available at short notice in drums or road tank wagons. Send for samples and prices.

ROY WILSON, DICKSON LTD
41 NORTH JOHN ST, LIVERPOOL 2 Tel: Central 7691

INDEX OF ADVERTISERS

	Page		Page
A.B. Mould & Construction Co. Ltd.	ix	Loxa (Great Britain) Ltd.	—
A.C.E. Machinery Ltd.	ixv	Lords Oil & Grease Co. Ltd.	iii
Ashbrook & Co. (Engineers) Ltd.	ixvi	Lenscrafts Ltd.	iv
Atlan, E. P., & Co. Ltd.	ixxi	Leventon (Industrial) Ltd.	viii
Allied Building Commodities	—	Lillingston, George & Co. Ltd.	viii
Asclap Building Products Ltd.	xxi	Lind, Peter, & Co. Ltd.	v
Atlas Stone Co. Ltd.	xiii	Lowden, George, & Son Ltd.	—
Barrow, A. & C. Ltd.	—	McCall & Co. (Bursfield) Ltd.	iii
Berry's Engineering Co.	ixviii	McCall's Macalloy Ltd.	xiii
Boulders Equipment Ltd.	—	McKinney Foundations Ltd.	xviii
Boyer, Wm., & Sons Ltd.	i	McKinney (Continental) Ltd.	—
Braythwaite & Co., Engineers Ltd.	xiv	Madgett Ltd.	—
B.R.C. Engineering Co. Ltd.	ixxviii	Manser, A. H., Ltd.	viii
Brett, Robert, & Sons Ltd.	—	May & Butcher Ltd.	xviii
British Oxygen Co. Ltd.	—	Milbank Floors Ltd.	ixix
British Steel Piling Co. Ltd.	—	Milbank Machinery Co. Ltd.	ixxi
Building & Construction Co. Ltd.	—	Mills Scaffold Co. Ltd.	—
Byrd, A. A., & Co. Ltd.	ixxi	Modular Concrete Co. Ltd.	ixxi
Cable Cables Ltd.	ixxi	Mohr, A., & Co. Ltd.	ixxi
Calderonian Mechanical Handlings Co. Ltd.	viii	Mulcaster, Wm., & Co. (Contractors) Ltd.	ix
Carpin Engineering Co. Ltd.	xiii	Myers, Fred, Ltd.	viii
Castlehill Sand & Gravel Co. Ltd.	—	Omnia Constructions Ltd.	—
Cement Marketing Co. Ltd.	ixxiii	Overseas Commodities (Soc.) Ltd.	xix
Cement & Steel Ltd.	xi	P.S.C. Equipment Ltd.	ixxi, ixvii
Christham, Alex. J., Ltd.	ixxviii	P.Z. Prefabricating Co. Ltd.	xiv
Chemical Building Products Ltd.	xxii	Pamley & Tibbitt Ltd.	—
Christall & Nisbett Ltd.	—	Pierres Ltd.	iv
Conroy, George, Sons & Co. Ltd.	—	Pittman, Sir Isaac, & Sons Ltd.	—
Colcrete Ltd.	xvii	Portland Ltd.	ixxi
Concrete Piling Ltd.	—	Powell Duffryn Timber Industries Ltd.	—
Concrete Paving Co. Ltd.	xiii	Prestressed Sales Ltd.	—
Concrete Pump Co. Ltd.	xix	Price, W., & Sons Ltd.	ix
Concrete Structures Co. Ltd.	—	Promerit Hire Co. Ltd.	xiv
Cowley, J. E., Ltd.	viii	Ramalan Steel Moulds Ltd.	ixx
Cowley, Wm., & Son Ltd.	—	Rover Car Co. Ltd.	—
Croydon Reinforced Firebricks Co.	—	Ross & Tompkins—Pauling Group	ixxviii
D.A. Models Ltd.	ixiv	Rylands Brothers Ltd.	ixxi
Dawson, J. & A., Ltd.	—	Sealcrete Products Ltd.	ixv
Davidsons Paper Sales Ltd.	ix	Sharp Jones & Co. Ltd.	—
De Jong	—	Simplex Concrete Piles Ltd.	ixxvii
Dickens, Stuart B., Ltd.	ixxi	Somerset Wire Co. Ltd.	xix
Douglas, Robert M. (Contractors) Ltd.	—	Spencer Wire Co. Ltd.	xix
Durature & Wire Ltd.	xviii	Stalls Ltd.	ixxi
Engineering Drawings & Construction Ltd.	ixxvi	Stone Precast Concrete Ltd.	i
Enston Bros.	vi	Ston B Paint Sales Ltd.	xix
Expansite Ltd.	ixx	Stone Court Ballast Co. Ltd.	ixxviii
Farr, A. E., Ltd.	—	Storke, Wm. T., & Co. Ltd.	xi
Flexible Drive & Tool Co. Ltd.	ixxviii	Structural Developments Ltd.	xviii
Fordville, Soc. Am., Inc.	xix	Stuart's Granolithic Co. Ltd.	ixxi
Ford Motor Co. Ltd.	xvii	Sunder & Dinning Brick Co. Ltd.	—
Franklin Ltd.	xv	Tarmac Ltd.	—
G.K.N. Reinforcements Ltd.	ixxi	Technical Paint Services	ixi
Glasgow, M. J. (Contractors) Ltd.	—	Tentor Bar Co. Ltd.	—
Goodie Engineering Ltd.	—	Thames Plywood Manufacturers Ltd.	xvi
Gurte Construction Co. Ltd.	ixvi	Teleman & Co. Ltd.	—
Hall & Co. Ltd.	—	T.P. Polyethylene Containers Ltd.	—
Head Wrighton Thermal Ltd.	ixxi	Thet Gravels Ltd.	ixxvii
Hilton Gravel Ltd.	—	Thiton Engineering Co. (Sales) Ltd.	ixvii
Holmes & Co. Ltd.	—	Truck-Mix (Midlands) Ltd.	—
Hosby & Co. Ltd.	—	Tynne Portland Cement Co. Ltd.	ixxvii
Huntley & Spence Ltd.	—	Unbrut Division of Sarnley-Sherlock Ltd.	—
Imperial Cement (Reading) Ltd.	—	Volkman, O. A.	i
Imperial Chemical Industries Ltd.	—	Walker Wright & Co. Ltd.	ixxi
Johnson, Richard, & Newsum Ltd.	xii	Wellbeck Trading Co. Ltd.	—
Jones, T. C., & Co. Ltd.	—	Wellman Bros. Ltd.	—
Kellogg Ltd.	ix	Whitwood, Joseph, & Co. Ltd.	ixvii
Kramer-Greenwood & Co. Ltd.	ixv	Whitwood Wire Co. Ltd.	—
Kiss, J. L., & Co. Ltd.	—	Whithead Iron & Steel Co. Ltd.	x, xi
Kiss, J. A., & Co. Ltd.	xvi	Whitley Moran & Co. Ltd.	xvii
Lafarge Aluminium Cement Co. Ltd.	ix, ixxi	Wilson, Rev, Dickson Ltd.	iii
Lawler Ayres & Co. Ltd.	ixxiv	Winget Ltd.	iv
Laws & Son (Stained) Ltd.	—	Wolf Electric Tools Ltd.	ixxi
		Yorkshire Hennessey Contracting Co. Ltd.	vii

SULPHITE LYE

IN LIQUID FORM

**an important additive for
concrete · grout · and most
forms of ground treatment**

Liquid Sulphite Lye is an effective cement expander, whereby cement shrinkage is obviated, leaving the concrete free from shrinkage cracks. For mass concrete it avoids the deleterious effects of thermal contraction and shrinkage. It is also invaluable for grouting work, and for prestressing cable ducts it ensures that when the grout is set it always completely fills the cable duct and other apertures. Its qualities for ground treatment and tunnelling work have also been proved on important contracts.

Liquid Sulphite Lye is the most effective and economical material for producing air-entrained and colloidal concrete, and will satisfy the most exacting requirements for this class of work.

Sulphite Lye is available at short notice in drums or road tank wagons. Send for samples and prices.

ROY WILSON, DICKSON LTD
41 NORTH JOHN ST, LIVERPOOL 2 Tel: Central 7691

PIERHEAD

**Pre-cast floors
are being used
throughout
the contract for
TRAWSFYNYDD
NUCLEAR POWER
STATION**

PIERHEAD

A
MEMBER OF
THE
BOOTH GROUP

**SPEKE BOULEVARD,
LIVERPOOL 24.**

ALSO AT LONDON AND BIRMINGHAM.

DRILLED FOUNDATIONS



Architects
Consulting Engineers
Main Contractors

Sir John Burnet, Tait and Partners
One Arup and Partners
Fretledge and Cally Limited

A modern office block which is being erected
on our drilled foundations at Vauxhall Bridge
Rd London for Chesterfield Properties Limited

We have modern mobile plants which can
drill foundations of various diameters up to
depths of 100 feet or more. Tel. Abbey 7361
or send your enquiries to

PETER LIND

Peter Lind and Company Limited Romney House Tufton Street London SW1

MAIN SUPPLIERS OF THE CONCRETING SAND AND AGGREGATES FOR THIS VAST PROJECT



**E
N
S
T
O
N
BROS**

We have large stocks of aggregate and washed sand available for any size of contract.

Accurately graded to your requirements, and promptly delivered to schedule by our fleet of trucks, our aggregates and service are first-class. We will be pleased to send samples, and to quote for any quantity.

We are also specialist manufacturers of precast concrete, and full details of our large range of products will be sent on request. Concrete cube strength at 28 days over 11,000 lb. sq. in.

TRAWSFYNNOD NUCLEAR POWER STATION

Consulting Architect: Basil Spence, Esq., O.B.E., T.D., A.R.A., A.R.S.A.

Consulting Engineers: Messrs. Mott, Hay & Anderson


Civil Engineering Contractors: Nuclear Civil Constructors Ltd.

**LLWYN ISAF
QUARRY**

ENSTON BROS

LLWYN ISAF QUARRY, UPPER CLYNNOG

CAERNARFONSHIRE, TRAFALGAR, CLYNNOG FAWR 297/8 & 393



Reconstruction of Whitehills Harbour

by

THE

YORKSHIRE

HENNEBIQUE

Contracting Company Limited

Established 1904

CIVIL ENGINEERING CONTRACTORS

HENNEBIQUE HOUSE

YORK

Telephone: York 54656 (4 lines)

Boosting storage space capacity—the high-speed **HYSTER** truck moves and stacks faster and more smoothly.



Model YE40 Diesel

Photo by courtesy of Messrs Lignacite (South Eastern) Limited, Nuffield, Nr. Baitle, Sussex



Hyster **SpaceSaver** Lift Trucks from 1,000 lb. to 10,000 lb. capacity; Challenger Lift Trucks from 1,000 lb. to 46,000 lb.; diesel, L.P.G. or petrol. Hyster Ransomes—Electric Lift Trucks from 1,000 lb. to 6,000 lb. capacity, with complementary range of cranes, towing tugs, platform trucks, reach trucks, straddle trucks, hydraulic and mechanical attachments.

'Hyster' and 'Space-Saver' are Registered Trade Marks

The Authorized Hyster Dealers

A. H. MASSER, LIMITED
CALEDONIAN MECHANICAL HANDLING
CO. LTD

FRED MYERS LIMITED
A. E. COULTER LIMITED
LEVETON (Industrial) LIMITED

East Wall Road, Dublin, E. Telephone: Dublin 12891

21, Old Castle Road, Glasgow, S.A. Telephone: Gonylas 2332/4
Branch office: Luton, Beds.

24, Brunel Street, London, W.1. Telephone: Hyde Park 9211

Branch offices: Service depots: Cardiff, Glasgow, Southampton, Birmingham, Lough (Staffs.)

29-34 Whitfield, Belfast, E. Telephone: Belfast 164564

Woodstock Road, Nottingham Telephone: Nottingham 12259
Branch depots: Newcastle, Ripon and York.

PSR* SEALERS

KELSEAL manufacture a tremendous range of Sealing materials designed to suit various applications in a variety of industries.

Experience gained from solving problems concerning the effective sealing of reservoirs, dams, motorways, piles and "metal to concrete" structures has proved the value of our P.S.R. (Polysulphide Synthetic Rubber) sealers and primers.

The large permanent range of Jointing compounds include Butyl Rubber and Epoxy 2-part compounds.


We will be pleased to supply technical information concerning your particular sealing problems.

* *Polysulphide Synthetic Rubber*

**Watertight answer
to Concrete Sealing
Problems!**

KELSEAL LTD., VOGUE HOUSE, HANOVER
SQUARE, LONDON, W.1. • Hyde Park 1411

KELSEAL



.....

have been regularly used

.....

by leading Contractors for

.....

reinforced concrete work

.....

since 1903

.....

We were the pioneers in the supply of steel bars for reinforced concrete work and have given to the industry over 50 years of unbroken service, unequalled for quality and dependability. Contracts on which WHITEHEAD STEEL has been used include some of the largest and most important in the country.

We can supply mild steel with an ultimate tensile stress of 28/33 tons to the square inch, medium tensile 33/38 tons to the square inch, and high tensile 37/43 tons per square inch.

We can also supply high tensile bars 40/45 tons to the square inch with a minimum yield of 60,000 pounds per square inch.

THE

WHITEHEAD IRON & STEEL CO. LTD.**NEWPORT**

Tel. No. NEWPORT (4481) (PBX)


MON

LONDON OFFICE: Steel House, Tothill Street, S.W.1. Telephone: Whitehall 2984/5.

BIRMINGHAM OFFICE: King Edward House, New Street, 2. Telephone: Midland 0412/3.

MANCHESTER OFFICE: Chronicle Buildings. Telephone: Blackfriars 1603/4.

GLASGOW OFFICE: 50 Wellington Street, C.2. Telephone: Central 1528.




POWER BAR CUTTERS

The BRRL 50A model, illustrated above, will meet all requirements for high speed, economy, and simplicity of operation. This high-speed shearing machine will cut mild steel rods up to 2 in. diameter. It is of robust construction yet portable in view of its compact arrangement, and is powered by electric motor and self-tensioning Vee-belt drive. The moving blade is in continuous action and makes 28 cuts per minute; 2-in. diameter bars require one cut only. The static blade is housed in a specially designed seating which spreads the shearing thrust over a wide area, thus reducing wear and considerably lengthening the life of the machine. Diesel-driven machines also available. Let us send you full details.

CEMENT & STEEL, LTD., SECOND AVENUE, CHATHAM, KENT

Telephone: Chatham 45580. Telegrams: Cambelgi, Chatham.


THE MACALLOY THREADED ANCHORAGE



The nut and thread anchorage is positive and without slip; it does not need a critical setting up and is quickly stressed. One can stress and re-stress at any time before the duct is grouted, and partial prestressing may with care be applied by hand so saving a bit on jack hire and allowing castings to be moved quickly off the base plate, so giving a rapid turn-round of moulds. (Jack hire is not expensive however).

The nut can finish anywhere on the thread, allowing a 2 in. tolerance in the length of members; this is especially useful when a number of units are stressed together, or when transversely stressing bridge decks and that sort of thing. Couplers can be added at any time to a bar already stressed to give continuity throughout framed structures and the like; the same, a greater, or a lower prestress can be continued beyond the coupler.

So long as a bar has not been grouted, the prestress can be checked or adjusted by applying the jack; besides the very considerable practical advantage of this, the check can be used to eliminate uncertainty. The robust and positive nature of a nut and thread is easily understood by the user and so many checks are provided that one can be sure that careful design is not wasted by uncertainty in execution. Such is the basis of real economy.



PRESTRESSING
STEEL
by **McCALLS**

McCALLS MACALLOY LIMITED

TEMPLEBOROUGH • SHEFFIELD • ENGLAND • P.O. BOX 41

Telephone: ROTHERHAM 2076 (P.B. Ex 8 lines)

LONDON: SLOANE 0428 • BIRMINGHAM: ACOCKS GREEN 0229

PORTSMOUTH: COSHAM 78702 • MANCHESTER: BLACKFRIARS 1018



the modern method of



PRESTRESSED CONCRETE DESIGN AND CONSTRUCTION

**FOR
INSITU AND
PRECAST
STRUCTURES
OF ALL TYPES**

This system is described and illustrated in our Catalogue, together with some of the many important contracts on which it has been used. Engineers and Contractors interested in the latest developments should send for a copy.


THE PZ PRESTRESSING CO. LTD.

BURCOTT LODGE, BURCOTT, WING, LEIGHTON BUZZARD.


TELEPHONE: WING 286

FRANKI facts

BOROUGH OF BEDFORD CENTRAL AREA RE-DEVELOPMENT



STRATA



PROBLEM

The nature of the strata in this re-development area precluded the use of ordinary footings for twelve-storey structures, and deep mass concrete foundations would have proved too costly in view of the high water table and the depth of excavation that would have been necessary to carry the high concentrated loading.

SOLUTION

In the face of keen competition, Franki driven type in-situ piles were selected for this contract as they offered:—(1) maximum security coupled with (2) speed of execution—as many as nine or ten piles were driven by one machine in a day, and (3) economy; all of which are of paramount importance with projects of this nature.

Contract No: 3088 • Client: Bedford Corporation
 Borough Engineer and Surveyor: F. W. Dawkes, B.Sc. (Eng) A.M.I.C.E., M.I.Mun.E., A.M.T.P.I.
 Chief Assistant Architect: C. A. E. Beecher, A.R.I.B.A.
 R.C. Engineers: Truscon Limited • General Contractors: Drabble Construction Co. Ltd.
 Type of Structure: Twelve-storey Flats • Number and Type of Piles: 354 Franki Driven
 Working Load: 60 tons • Average Length: 17' 6"



FRANKI

At your Service throughout the World

FRANKIPILE LIMITED • 39 VICTORIA STREET • LONDON S.W.1 • TEL: ABBEY 6006/9

THAMES NOILPLY

smooth
shuttering
without
oiling



These 14 ft. columns for an office and warehouse block in City Road, London, were poured in one lift. Photo by courtesy of the contractors: BIGGS & HILL LTD., London.



Noilply moulds for 150 ft. run of floor and roof beams made for the Mersey Dock and Harbour Board, Liverpool. Manufactured by: MILBANK FLOORS LTD, GREAT WALTHAM, CHELMSFORD, ESSEX.

Thames Noilply gives the smoothest surface of any shuttering entirely without oiling. This important saving in oil and labour has been achieved by facing the plywood shutter with a special glossy plastic which completely repels concrete and leaves surfaces superbly smooth. With reasonable handling Noilply shuttering can be used time and again without oiling. Later, it continues to give long service in the traditional way. The reverse side is balanced by a standard plastic. Try Noilply on your next contract and see how quickly it repays its cost.

Supplied only through trade channels.

THAMES - NOILPLY

THAMES PLYWOOD MANUFACTURERS LTD


Herts Lane · Barking · Essex · Telephone: Rippleway 5511

TA 4196

A LIGHTING ENGINEER'S BEST FRIEND IS A FORD ENGINE

Ford Industrial engines are the heart of all kinds of generating sets—large, small, stationary, mobile—doing all kinds of responsible jobs—standing-by for emergencies in schools, cinemas and hospitals, providing on-site light and power in out-of-the-way places, giving light for film and TV units on location. For such jobs Ford Industrial engines are the best possible choice. They are tough, hard-working and utterly reliable, and they have behind them the incomparable Ford Service Organisation—a world-wide chain of factory-trained engineers with stocks of genuine Ford parts at their finger-tips. Send us the coupon below for details of the Ford-powered generator sets that are available.

FORD
SPELLS POWER



Please send me details of Ford-powered Generator sets

Type of set required

YOUR FIRM'S NAME

For the attention of Mr

ADDRESS

TO: FORD INDUSTRIAL ENGINE DIVISION • DEPT G5b/L6. • SOUTH OCKENDON • ROMFORD • ESSEX • ENGLAND

TRITON

REGD. TRADE MARK

VIBRATING SYSTEMS



vibrating precast concrete on the site
with mobile or fixed equipment . . .

Triton vibrating systems provide the Contractor with a completely planned vibrating unit for the production of precast concrete on the site. Our technical advice service will be pleased to suggest a comprehensive plan, using both mobile "Vibra-Lifta" tables and fixed tables (illustrated below) which will show the economy and efficiency to be obtained from using a Triton Vibrating System on the site.



The top illustration shows two Triton mobile "Vibra-Lifta" tables vibrating a 25-ft. precast beam. These "Vibra-Lifta" tables can be moved at will to any part of the site. The second illustration shows two Triton fixed tables vibrating a 15-ft. precast purlin. These tables can be mounted on concrete blocks of any required height. Complete technical details of these are available on request.

THE TRITON ENGINEERING CO. (SALES) LTD

KINGSNORTH INDUSTRIAL ESTATE, WOTTON ROAD, ASHFORD, KENT

Telephone: Ashford 2051-2-3 Telegrams: Triton Ashford Kent

UNDERPINNING

RETAINING

CONSOLIDATING

PALI RADICE (ROOT-PATTERN PILES)

SYSTEMS PROVIDE THE CONCRETE ANSWER

There is a Pali Radice system of structural protection for foundations against any kind of underground movement. Patented systems of root pattern piles provide a most effective means of underpinning any building or structure, while our patented grid retaining wall system ensures the stability of existing structures during nearby deep excavations. The reinforcing action is very smooth and gradual and starts from the beginning of the work. Consolidation for upper structures does not interfere with the original room disposition and preserve existing artistic decorations, frescoes, mosaics, etc. Other patented methods are applied to the consolidation of various types of ground, and for the formation of water-tight diaphragms by casting reinforced concrete walls in the ground. Our extensive experience, and our constant development of new methods, enable us to tackle with confidence any problem connected with this type of work, however difficult or tricky the situation, and wherever it may be.

Soc An FONDEDILE INC

NAPLES—Via Verdi 35.
GENOA—Via Milano 40c.
PALERMO—Via E. Amari 32.
MILAN—Via Velasca 5.
ROME—Piazza Buenosaires 14.
ATHENS—12 Kolokotroni Str.
VIENNA—Strarkfriedgasse 25.

All enquiries in the U.K. to—

OVERSEAS COMMODITIES (SOC) LTD
2 LONDON WALL BUILDINGS LONDON EC2 Tel: London Wall 5276



IBECO

WATERPROOF PAPER

IN CONCRETE ROAD CONSTRUCTION

Recommended qualities for concrete work are IBECO No. 40 to BS 521/1949 Class B and IBECO No. 60, the choice depending on the stresses involved. The former fully meets the specification at the lowest possible cost. As well as preventing seepage from the mix IBECO also checks the upward penetration of harmful acids and other chemicals frequently occurring in subsoils. It also has useful applications as a curing overlay. There is no free bitumen in IBECO to sweat out under exposure to hot sun. We will gladly send samples on request.

DAVIDSON'S PAPER SALES LTD.

LONDON: 82/84 St. John St. E.C.1 LIVERPOOL: 31 North John St. 2. LEEDS: 9 Albion St.

NEWCASTLE: 42 Corporation St. GLASGOW: Laird Place, Bridgeton, SE.

EDINBURGH: Boroughloch Square. DUNDEE: 24 Lamb's Lane. ABERDEEN: 4 Trinity Quay.


HEAD OFFICE: Mugiemoss Mills, Bucksburn, Aberdeen.

For the essential retention of water in a concrete mix to ensure sound setting and hardening, careful contractors are more and more depending on IBECO... Like no other waterproof paper, IBECO is waterproof throughout its texture. The proofing bitumen is part of the paper itself. Folding, creasing, even heavy trampling will not impair IBECO's impermeability... It's easy and quick to handle—speeds the work as well as lowering its cost and ensuring a better job.

Remember IBECO for contracts in hand and in prospect.



STANDARD PRESTRESSED CONCRETE BEAMS . . .



WHITSON BRIDGE

*Designed by
Transmission
Project Group of
C.E.G.B.*

*Contractors:
A. Jackman &
Sons Ltd*

...SIMPLIFY BRIDGE BUILDING


The bridge at Whitson shown above is the first to be built incorporating the new standard prestressed concrete beams. These 48 ft. long precast beams supplied by us conform in every way to the standards recently laid down by the Prestressed Concrete Development Group, and prove yet again that our techniques and methods are fully up to date in every possible way.

ANGLIAN BUILDING PRODUCTS LTD

Designers and Manufacturers of Reinforced and Prestressed Concrete Units

ATLAS WORKS LENWADE NORWICH

LONDON OFFICE 100 BROMPTON ROAD SW 3



OUTSTANDING BUILDING ...

Outstanding Products

CHEMICAL
BUILDING
PRODUCTS LTD
Warple Works
Cleveland Road
Hemel Hempstead
Herts


Telephone:
BOXMOOR 4900
(5 lines)
Telegrams: Prolithu
Hemel Hempstead

PROLAPIN Liquid Cement Waterproofer
LITHURIN Concrete Floor Hardener
QUICKSocrete P. Q. & D. Rapid Hardeners
and Setters

WETEXI 'S' Colourless Silicone Waterproofer
CONPLAST Concrete Plasticiser
CONPLAST 'W' Anti-freeze and Plasticiser
CONBEX Plasticised Expanding Grouting Material
CEBEX 112 Mortar Improver
CEBEX 113 Expanding Grouting Material
CEBEX 124 Multi-purpose Slurry Liquid
ROAD CONPLAST Air Entrainer and Plasticiser
LIFTOYL Floor Cleaner and Degreaser
ORKIT & TEKTAM Bituminous Coating and
Compounds
CONCURE Concrete Curing Agent
NITOLUX & ROBRITE Paints

NEW !! SCREEDEx the ideal Screed Additive.

CHEMICAL BUILDING PRODUCTS LTD



for
economy in
bored foundations

DOWN TO 110 FEET

McKINNEY

- * Underreamed
- * Greater bearing area
- * Fewer piles
- * Reduced costs

*May our design engineers assist you with
your foundation problems?*

A **LAING** COMPANY

McKINNEY FOUNDATIONS LIMITED

Manor Way, Boreham Wood, Hertfordshire. Tel: Elstree 2854



TAKE A GOOD LOOK AT THE SURFACE

The water tower illustrated has a protective Stic B stone covering stipple finish similar to that shown in the smaller photograph. Treated in this way it is completely protected from the atmosphere and will require no further attention for many years. Stic B can

be applied direct to new or old concrete and most other building surfaces. No other material affords such lasting protection, while remaining so easy to apply.


Descriptive literature available.

STIC B PAINT SALES LTD.

99 WANDSWORTH ROAD,

VAUXHALL, S.W.8

Telephone: RELiance 5566/2178 Telegrams: Sticbeelim, London, S.W.8



An Electrically Driven PC3 Concrete Pump with remixer. Capacities from 20 to 24 cu. yds. per hour. Ranges actually obtained 135 ft. vertical or 1,500 ft. horizontal. Also smaller model PC4—8-10 cu. yds. per hour.

EFFICIENT RECONDITIONING SERVICE

CONCRETE BY PUMP AND PIPELINE

- The most efficient method of placing concrete.
- Life of Pump practically indefinite: all essential surfaces in contact with concrete are renewable.
- Pumpable concrete must of necessity be good concrete.
- Pump and Mixing Plant can be located at the most convenient position within the pumping range.
- The continuous output of the Pump at a constant speed governs the working of the whole concreting gang.

THE REGISTERED TRADE MARK OF

PUMPCRET

THE CONCRETE PUMP COMPANY LIMITED

THE CONCRETE PUMP COMPANY LTD


4 STAFFORD TERRACE, LONDON, W.8

Telephone : Western 3546

Telegrams : Pumpcret, Kens, London

PSC

HYDRADUCT SHEATH



HYDRARIGID

HYDRARIGID

HYDRAFLEX

Hydraduct is an extremely robust form of sheathing for prestressing tendons and meets the most stringent requirements of Designers and Contractors; problems which may be encountered in transportation and site handling have been carefully considered.

PSC GROUT INJECTION EQUIPMENT



◀ P.S.C. hand-operated diaphragm, direct displacement grout pump with electrically operated stirrer.

P.S.C. power-operated grout injection pump. ▶




The subject of cable grouting is one that P.S.C. Equipment Limited have studied intensively and for which a range of equipment has been developed.

PIONEERS OF PRESTRESSED CONCRETE IN GREAT BRITAIN

P.S.C. Equipment Limited, members of the Freyssinet International Organisation, have available a range of prestressing systems including Freyssinet MultiWire, Freyssinet MultiStrand—FreyssiStrand, P.S.C. MonoWire, P.S.C. MonoStrand and P.S.C. Pretensioning. Full details and complete technical information are always available on request.

FREYSSINET

RUBBER BRIDGE-BEARINGS



... the modern method of supporting bridges and other civil engineering structures. They are more economical and technically superior to traditional steel bearings and are widely recommended. Freyssinet bearing pads are of unit bonded construction. The design of the pads is based on the relationship between loads, displacements and rotations, and, as no moulding is required, each case is treated as unique and the proposed pad calculated accordingly. The highly satisfactory behaviour of this type of pad has been proved by tests and by observation on over 500 bridges on which they have been used. Technical questionnaire forms are available on request.

FREYSSINET

FLAT JACKS



Ref.	Outside Diameter (inches)	Maximum Force (tons) at 2,000 lb./in. ²
07	2.75	3
12	4.72	9
15	5.90	17
22	8.66	41
25	9.84	54
27	10.4	64
30	11.8	81
35	13.8	114
42	16.5	168
48	19.7	245
60	23.6	357
87	34.2	772
92	36.2	866

These hydraulic jacks of unusual and unconventional design permit enormous forces to be exerted where the movement required is small. They have considerable application in underpinning, levelling, and thrust control in engineering structures.

PSC



EQUIPMENT LTD

HEAD OFFICE AND WORKS: ARUNDEL ROAD, INDUSTRIAL TRADING ESTATE, UXBRIDGE, MIDDLESEX

Telephone: Uxbridge 35241

"CONCRETE SERIES"

BOOKS ON FOUNDATION ENGINEERING

DESIGN AND CONSTRUCTION OF FOUNDATIONS

By G. P. MANNING, M.Eng., M.I.C.E.

A dissertation, with much practical data, on the design of most types of foundations, including notes on constructional operations and materials. Many examples drawn from the Author's extensive experience.
226 pages. Numerous diagrams, working drawings, design charts etc.

Published July 1961

Price 24s.; by post 25s.

In Canada and U.S.A. 6 dollars.

FOUNDATION FAILURES

By C. SZECHY (Professor of Foundation Engineering, Budapest)

The author examines the causes of the failure, due to defective foundations, of numerous structures throughout the world. A useful guide to the avoidance of trouble.

Published March 1961

115 pages.

Price 20s.; by post 21s.

123 diagrams and photographs.

In Canada and U.S.A. 5 dollars.

REINFORCED CONCRETE PILING AND PILED STRUCTURES

By F. E. WENTWORTH-SHELDON, W. S. GRAY, B.A., and H. W. EVANS.

Describes the design, manufacture, and driving of precast concrete piles. Design of piled structures with examples and illustrations. Design data in accordance with the latest British Codes of Practice.

Second Edition. Published 1960

149 pages, 116 illustrations, 17 tables.

Price 18s.; by post 19s.

In Canada and U.S.A. 4 dollars.

RAFT FOUNDATIONS.—THE SOIL-LINE METHOD

By A. L. L. BAKER, D.Sc. (Tech.), A.M.I.N.S.T.C.E.

Describes in detail, with worked examples, the Soil-Line Method, a practical and economical way of taking into account variation of earth pressure.

Revised Edition. Published 1957

148 pages, 89 illustrations.

Price 12s.; by post 13s.

In Canada and U.S.A. 2-80 dollars.

To be Published Shortly

AN INTRODUCTION TO DEEP FOUNDATIONS AND SHEET-PILING

By DONOVAN H. LEE, M.I.C.E., F.A.S.C.E., M.I.Mech.E.

This book is the successor to the author's "Sheet Piling, Cofferdams and Caissons". It is much enlarged and now deals with soil investigation, bearing piles, and sub-aqueous tunnels, as well as making and driving sheet-piles, the design of sheet-pile walls, and the design and construction of cofferdams, cylinders and open and pneumatic caissons. A feature is the numerous examples of actual works throughout the world.

260 pages.

Price 20s.; by post 21s. 2d.

Numerous diagrams and photographs.

In Canada and U.S.A. 5 dollars.


For complete particulars of these and other books in the

"CONCRETE SERIES"

dealing with all aspects of design and construction in reinforced and prestressed concrete write to

CONCRETE PUBLICATIONS LTD.,
14 DARTMOUTH STREET, LONDON S.W.1

You get the lowest relaxation using **SOMERSET** **STABILIZED** Prestressing Wire



COMPARATIVE RELAXATION GRAPH Initial Stress 80 tons/sq. in.
(Drawn wire in the stress relieved and stabilized condition)

- ★ Somerset Wire complies with B.S. 2691
- ★ Is available in plain, indented or helically crimped forms
- ★ Has stable elastic characteristics


STABILIZED by a patented 'Somerset' process

SOMERSET WIRE COMPANY LIMITED

Pengam Moors, Cardiff (Cardiff 37485)
Bridgwater, Somerset (Bridgwater 3001)



Waterstops?



The New Underpass, Hook Road constructed by William Old Limited for the Surrey County Council

EXPANDITE
LIMITED

**CHASE ROAD, LONDON, N.W.10. Tel: ELGar 4321 (10 lines) Telex 25420
ELGar 1551 (10 lines)**

Trafford Park Road, Manchester 17 Telephone: Trafford Park 1285/6

36 Great North Road, Newcastle-upon-Tyne 2 Telephone: Newcastle 23992

Eire: EXPANDITE (IRELAND) LTD., Greenhills Road, Walkinstown, Dublin Telephone: 501512

ASSOCIATES AND DISTRIBUTORS THROUGHOUT THE WORLD

Expandite Limited produce a complete range of efficient Rubber and PVC Waterstops for every type of joint. Made in various designs and lengths, they are accepted as being the most effective and economical method of ensuring watertight structures.

Expandite Waterstops are specified by architects the world over because, unlike metal waterbars, they are not subject to corrosion and will not fracture with movement.

Not content to rest on their laurels, Expandite are constantly introducing new developments. The HYDROFOIL (PVC) revolutionary design combats all seepage, and is suitable for walls, floors, reservoirs, sewage works, ponds, etc. where limited movement may occur.


If you need advice on any problem concerning Waterstops and their most effective use, the Expandite Technical Service Department is always at your service. Please contact us.

**For the Royal
Burgh of Inverness
a modern new bridge of...**

RYLANDS BROTHERS LTD., WARRINGTON, LANCASHIRE.

PRESTRESSED CONCRETE using RYLANDS HIGH TENSILE STEEL WIRE


Replacement of the 104 years old suspension bridge over the River Ness has been necessitated by the prolific growth of motor traffic. The new 245 ft. long, 3 span bridge is designed to carry the heaviest traffic loads laid down by the Ministry of Transport, and to achieve this end Rylands 0.276 inch diameter wires in made-up cables of 12 wires each cable are employed for the prestressing of the beams.



Consulting Engineers: Sir M. MacDonald & Partners, Lion House, Red Lion Street, London W.C.1.

Contractors: Duncan Logan (Contractors) Ltd., Muir-of-Ord, Ross-shire.

Waterstops ?



The New Underpass, Hook Road constructed by William Old Limited for the Surrey County Council

EXPANDITE
LIMITED

Expandite Limited produce a complete range of efficient Rubber and PVC Waterstops for every type of joint. Made in various designs and lengths, they are accepted as being the most effective and economical method of ensuring watertight structures.

Expandite Waterstops are specified by architects the world over because, unlike metal waterbars, they are not subject to corrosion and will not fracture with movement.

Not content to rest on their laurels, Expandite are constantly introducing new developments. The HYDROFOIL (PVC) revolutionary design combats all seepage, and is suitable for walls, floors, reservoirs, sewage works, ponds, etc. where limited movement may occur.

If you need advice on any problem concerning Waterstops and their most effective use, the Expandite Technical Service Department is always at your service. Please contact us.

**CHASE ROAD, LONDON, N.W.10. Tel: ELGar 4321 (10 lines) Telex 25420
ELGar 1551 (10 lines)**

Trafford Park Road, Manchester 17 Telephone: Trafford Park 128516

36 Great North Road, Newcastle-upon-Tyne 2 Telephone: Newcastle 23992

Eire: EXPANDITE (IRELAND) LTD., Greenhills Road, Walkinstown, Dublin Telephone: 501512

ASSOCIATES AND DISTRIBUTORS THROUGHOUT THE WORLD

**For the Royal
Burgh of Inverness
a modern new bridge of...**

RYLANDS BROTHERS LTD., WARRINGTON, LANCASHIRE.



PRESTRESSED CONCRETE using RYLANDS HIGH TENSILE STEEL WIRE

Replacement of the 104 years old suspension bridge over the River Ness has been necessitated by the prolific growth of motor traffic. The new 245 ft. long, 3 span bridge is designed to carry the heaviest traffic loads laid down by the Ministry of Transport, and to achieve this end Rylands 0.276 inch diameter wires in made-up cables of 12 wires each cable are employed for the prestressing of the beams.



Consulting Engineers: Sir M. MacDonald & Partners, Lion House, Red Lion Street, London W.C.1.

Contractors: Duncan Logan (Contractors) Ltd., Muir-of-Ord, Ross-shire.




Illustration above shows some of the post-stressed bridge beams, each 80 ft. long and weighing 35 tons, produced by Anglian Building Products Ltd., for British Railways, Midland Region. Main Contractors: Messrs. Leonard Fairclough Ltd.

80 - ft. BEAMS
cast in
WOODEN
MOULDS
supplied by

MAY & BUTCHER LTD

SPECIALISTS IN TIMBER SHUTTERS AND MOULDS FOR CONCRETE

More and more Contractors and Precast Concrete Makers in all parts of the country are taking advantage of the first-class service we offer in the supply of timber shutters and moulds to any design and size. This service has proved over and over again that by ordering your shutters and moulds from us you effect every possible saving in time, labour and money. However intricate the shutter or mould, you are assured of accuracy in every detail and a product with long trouble-free life. Shutters and moulds can be supplied with a plastic lining if desired. Full details of this class of work carried out by us are available on request.

HEYBRIDGE BASIN, MALDON, ESSEX.

TELEPHONE: MALDON 698/9

"Your call to CMC
about **SULFACRETE**
Mr. Gilliatt!"



☛ Thank goodness! At last he's dealing with Blue Circle. Honestly, you should have seen him last week! Couldn't even get enough of it. I thought he'd go mad! Beats me why he didn't go for Blue Circle in the first place. I thought everyone did.☛

SULFACRETE The only Sulphate-resisting Portland Cement which has given proved protection in practice and in exposure tests over the last twelve years. *Good dense concrete can, by using Sulfacrete, be made proof against concentrations of sulphur trioxide (SO₃):*

In ground water—500 parts per 100,000 or 0.5% per weight.
In soil or clay—2.0% per weight.

Information on the major areas in Great Britain where the soil is known to contain sulphates is available from our technical department.

See **CMC** about Cement!

Make use of our technical service. For all information please write to:

THE CEMENT MARKETING COMPANY LTD. PORTLAND HOUSE, TOTHILL STREET, LONDON, SW1 • Telephone: YATe Gallery 3459
G. & T. EARLE LTD., HULL • Telephone: HULL 59121 (Selling Organisations of The Associated Portland Cement Manufacturers Ltd.)

LACO BAR BENDING AND CROPPING MACHINES

The LACO BAR BENDERS

are made in capacities up to 2" diameter. Several bars can be bent simultaneously.

MAIN FEATURES

Model LB.900


Two turntables revolve simultaneously. The fast at more than 10 r.p.m. enabling a 1" hook to be bent in 3 seconds.

Feeding: Bars are fed into the machine from left or right; hooks are made clockwise or anti-clockwise.

Automatic Stop: Turntables can be set to stop automatically at any angle to an accuracy of $\frac{1}{8}^{\circ}$.

Maintenance negligible. All bearings are ball or roller throughout. Gears are of steel and precision cut. All shafts, even the slowest, are fitted with grease-packed ball bearings.

Fitted with either electric motor, gasoline engine or diesel engine.



The LACO BAR CROPPERS

in all capacities up to 2" diameter, provide the quickest and safest method of site cropping.

MAIN FEATURES

Oil is circulated in closed circuit and, whilst machine is in operation, abundant positive lubrication is assured.

No damage results from lack of oil and no special servicing required. If foot pedal is depressed when no bars are placed between cutting blades, the blades will automatically stop, thereby assuring a very important safety feature because no cut can be made involuntarily. NO OPERATOR HAS EVER BEEN INJURED BY THESE MACHINES. Machines available at prices lower than any other manufacturer in the World. Capacities from $1\frac{1}{4}$ " up to 2" diameter.



PROMPT DELIVERY AVAILABLE

Full details from

LAWLER AYERS & CO. LTD

Broad Street House, 54 Old Broad Street, London, E.C.2

Telephone: London Wall 6331

GATHURST VIADUCT

Monk are Main Contractors for this vital link in the new Motorway connecting **Monk** Birmingham with the Preston By-Pass.

James Drake, Esq., B.Sc., M.I.C.E., M.I.Mun.E., F.I.H.E., County Surveyor and Bridgemaister, Lancashire County Council, who are Agents for the Ministry of Transport.



A. Monk & Company Limited. Warrington and London. Offices at Hull, Middlesbrough and Stamford. Civil Engineering, Building and Reinforced Concrete Contractors.



for

COROBAR

REGD TRADE MARK


COLD WORKED HIGH TENSILE REINFORCEMENT

**MILD STEEL &
HIGH TENSILE WELDED FABRIC**

AN EFFICIENT SERVICE ASSURED
IN SUPPLY, BENDING & FIXING

**THE ENGINEERING DESIGN & CONSTRUCTION
COMPANY LIMITED**
REINFORCEMENT SPECIALISTS

OFFICES: ARDSHEL HOUSE EMPIRE WAY WEMBLEY MIDDX.
TELEPHONE: WEMBLEY 9474 TELEGRAMS: EDCON WEMBLEY



BUILD ON A SURE FOUNDATION

The modern piling techniques and systems of Simplex are backed by over half a century of experience. Schemes and quotations for piling or reinforced concrete foundations will be gladly supplied, without obligation, on request.



7 Lygon Place, Grosvenor Gardens, Westminster, London S.W.1. Tel: SLOane 9122/3,4



Model VP 350-A (Swivel Base or Barrow Mounting)

Prompt Delivery. Highly Competitive Prices. Genuine Service. Re-Sale Terms Available.

★ We operate a 48-hour Shaft Repair Service for all makes. Write to-day for 8-page fully descriptive Catalogue. Agents throughout the world.

30 years' experience in the design and manufacture of flex-shaft tools.

THE FLEXIBLE DRIVE & TOOL CO., LTD.

EDENBRIDGE, KENT. Telephone: 3385-6

LONDON OFFICE: 17 QUEENSBERRY WAY, S.W.7. Telephone: KENSington 3583

For Greater Strength, Firmer Bonding
and Better Surfacing of Concrete—

"BAXTUL"

Regd. Trade Mark

British Made

Extra-High Frequency

INTERNAL CONCRETE VIBRATORS

● The model illustrated here operates at 9,000 to 15,000 Vibrations per minute from low flexible shaft speeds of 4,500 to 7,500 R.P.M.

● Petrol or Electric Drive.

● Robustly built throughout and backed by genuine service.

● Fitted centrifugal clutch, long-life flexible drive and Vibrator.

This unique machine, with quick-change additional tools, can also be used for: SURFACING, WET-RUBBING CONCRETE, GRINDING, DISC SANDING, AND DRILLING (up to 1½" in Concrete, 1" in Steel, and 2" in Wood).

COPPER STRIPS

for expansion joints

All Reinforced Concrete Engineers recognise the advantages of using copper strips for sealing joints in concrete work. Copper is ductile, will not crack under repeated bending, is non-corrosive and is unaffected by wet concrete. We specialise in the supply of perforated copper strips of all required lengths and widths for expansion joints, and shall be pleased to submit prices against detailed specification.

ALEX J. CHEETHAM LTD.

MORTON STREET • FAILSWORTH • MANCHESTER

Telephone: FAILsworth 1115/6




A marriage has been arranged

For better or worse, budgerigars seldom choose their own partners—yet seem to get by remarkably happily with those they are given.

In Civil Engineering, the question of marrying materials often arises. Here, where the choice is open, we can only record that our metallic bonder, STERNSON 610, has featured in many a happy wedding—and has proved itself, without question, a bond that lasts.

It has been widely used, for example, in the laying down of factory floors,—to provide the vital, enduring link between the wearing surface and the main slab beneath.



The STERNSON range is only part of our family of products and whatever or wherever your concern is with top-class concrete, there is no wiser first step than calling on the experience of



STUART B. DICKENS LTD

Manor Way, Boreham Wood, Hertfordshire

Telephone: Elstree 2211

STORER'S



Sawing, Planing and Moulding Mills and Storage Yards at Barking

for

SOFTWOOD

Wm. T. STORER & CO. LTD.

Timber Importers and Merchants

ESTABLISHED 1913

Telephone: RlPpleway 0301 (10 lines)

RIVER ROAD - BARKING - ESSEX



Road bridge reconstruction over railway junction - Renwick Road Bridge, Barking




Sponsor:
British Transport Commission,
B.R. Eastern Region
Consulting Engineers:
Sir William Halcrow & Partners
General Contractors:
W. & C. French Limited

The Bridge at Barking, carrying Renwick Road across an area of railway track which was to form part of Ripple Lane marshalling yard, has been replaced by a bridge of greater span. The new bridge consists of two 50-ft approach spans and a central 137-ft span. The approach spans were formed from precast partially prestressed concrete inverted tee beams, placed in position, with insitu concrete added to the lower flange — stressing was then completed and concrete poured to deck level. The centre span was also of insitu partially prestressed concrete units, but was of cellular construction. 0.276 in diameter high tensile wire was used throughout and stress was applied by the Freyssinet system. The wire content of the complete project was in excess of 500,000 feet.

wire was essential—

Johnson's of course!

Richard Johnson & Nephew Limited, Manchester 11. Telephone East 1431



For compacting mortar cubes
for compression tests to

B.S. 12/1958, 146, 1370, 915

Automatic Time Control

"CAPCO"

H.F. VIBRATOR

"CAPCO" CONCRETE TESTING APPARATUS also includes:
Cube Moulds; Slump Cones; Tensile, Vicat and Cylindrical
Moulds; Compacting Factor Apparatus—Standard and Auto-
matic; Sieve Vibrators and Sieves; etc.

CAPLIN ENGINEERING CO. LTD
(ESTABLISHED 1918)

POLLEN HOUSE, 18/12 CORK STREET, LONDON, W.1

Phone: REGENT 0716. Grams: CAPLINKO, LONDON. Telex: 23255. Cables: CAPLINKO, LONDON. Works: IPSWICH.

**CONCRETE
PROOFING
Co. LTD.**

**GUNITE
SPECIALISTS**


Expert advice and schemes submitted for gunite
work of every kind. Complete information on
the various uses of gunite will be gladly sent
on request

116 Richmond Road, Kingston-upon-Thames, Surrey. Telephone: KINGSTON 7883 and 9253
And 10 Royal Crescent, Glasgow, C.3. Telephone: GLASGOW DOUGLAS 8891

For precast concrete floors consult **ATLAS**

manufacturers of the
OMNIA FLOOR
and other types of
precast flooring

easy to handle—palletised loads
quick assembly
no shuttering
monolithic character
good heat and sound insulation
fire resistant
long spans and heavy loadings
low weight
adaptable for services
economical




The Staff Theatre and Office Block, Kingway, London WC2 in which the Omnia Floor was used throughout, supplied by Atlas Stone.
Architect: Lewis Solomon, Kays & Partners
Consulting Engineer: John DeKromacker & Partners
Quantity Surveyor: Basil A. Cohen, FRICS
Contractor: Token Construction Co. Ltd



Our skilled staff are always ready to assist you in the initial design stages or they are available to carry out the complete design work to the architect's specification. Complete sub-contracts can be undertaken. For further information about the concrete floors write to us

The Atlas Stone Company Ltd.

Artillery House, Artillery Bow, London, S.W.1. Telephone: ABBey 3081-2-3-4



THE P.C.4 PUMCRET CONCRETE PUMP

CONCRETE BY PUMP AND PIPELINE

Specifications:

	Two Sizes	P.C.3	P.C.4
Capacities per hour, approx. . .		20-24 cu. yd.	8-10 cu. yd.
Range:			
Horizontal, approx.		1500 ft.	1250 ft.
or Vertical, approx.		135 ft.	125 ft.
Pipeline		6" i.d.	4 1/2" i.d.
Power required: Electric or Diesel		45 h.p.	25 h.p.

FOR HIRE

PUMCRET


THE REGISTERED TRADE MARK OF
THE CONCRETE PUMP COMPANY LIMITED

PUMCRET HIRE COMPANY LTD

4 STAFFORD TERRACE, LONDON, W.8

Telephone: Western 3546

Telegrams: Pumcret, Kens, London



*Architects: Robert Matthew & Johnson-Marshall F/A.R.I.B.A.
Consulting Engineers: J. Roger Preston & Partners.
Consulting Structural Engineers: Scott & Wilson, Kirkpatrick & Partners.*

New Zealand House, now being built in Haymarket, London, by Holland & Hannen and Cubitts (Gt. Britain) Ltd., is a building of 19 storeys supported by Braithwaite Cylinder Foundations 6' in diameter and sunk to a depth of over 90'.

BRAITHWAITE FOUNDATIONS & CONSTRUCTION LIMITED

(PROPRIETORS: BRAITHWAITE & CO. ENGINEERS LIMITED)

London Office: DORLAND HOUSE, REGENT STREET, S.W.1.

Telephone: WHItchall 3993. Telegrams: Bromkirk London S.W.1. Telex 23320

Experience COUNTS . .

WHITLEY MORAN AND CO. LTD. GUNITE SPECIALISTS

-And behind every job...25 years' experience in the scientific repair of engineering structures

5 OLD HALL ST. LIVERPOOL 3. 'PHONE: CENTRAL 7975/6
'GRAMS: Gunite, Liverpool, 3

May we PRECAST your STRUCTURAL COLUMNS

SAVE TIME *and* SAVE MONEY

J. A. KING & Co., LTD

181 Queen Victoria St., LONDON, E.C.4

Telephone: CENTRAL 5866 (5 lines)

Telegrams: Kinovique Cent London

THE GAMMON-MORGAN WATER-IN-SAND ESTIMATOR

for the
**ACCURATE,
SIMPLE AND
RAPID**

measuring of the
**WATER CONTENT
IN SAND**



MOISTURE VARIATIONS IN THE SAND

Engineers should specify that the concrete mix shall be adjusted for moisture variation in the sand, so that the total water in the batch shall consist of the water carried in the aggregates plus the water added in the mixer.

The most accurate, simple, and rapid means of measuring the water content in the sand. No weighing or chemicals are required, and an adequate sample is used. The GAMMON-MORGAN WATER-IN-SAND ESTIMATOR should be available alongside every mixer, so that the water content of every mix may be correctly gauged. Full details will be sent on request.

PRICE £4 4s. 0d. each
(12 Canadian or U.S. dollars).

CARRYING CASE £2 10s. 0d.
(7 Canadian or U.S. dollars).

Details from

COLCRETE LIMITED


GUN LANE · STROOD · KENT

Phone: Strood 78431/2/3

Whether it be an expansion
or construction joint—let . . .

DURAJOINT

take the strain



See what happens when the concrete contracts.

THE DURAJOINT

retains its close keying to the concrete beyond the flange nearest the centre. No other expansion joint gives this safeguard.

It takes care of shear as well!

Sole Manufacturers

DURATUBE & WIRE LTD

CENTRAL WAY (FAGGS ROAD), FELTHAM, MIDDX

Phone: FELTHAM 3453/6

Grams: DURATUBE FELTHAM



Today's basic constructional material is concrete. It is used in roads, offices, factories, warehouses, and every conceivable kind of building. But to do its job with complete efficiency, concrete must be strengthened. And this is where Spencer Mesh comes in. Made to B.S. requirements, this electrically-welded mesh is made only from high tensile steel wire. Strong. Reliable. And what is more, the wire is drawn by the Spencer Wire Company themselves, in their own mill. Spencer Mesh is supplied in standard square or oblong meshes, in either sheets or rolls. If you have a concrete reinforcement problem, get in touch with the Spencer Mesh people. You can be sure of really useful help.

SPENCER MESH



SPENCER WIRE • WAKEFIELD

Telephone Wakefield 6111

DaW961CCE



... Precast Concrete Piles

Preferred by constructional engineers for their unchanging supremacy, Stent Precast Concrete Piles have proved their qualities wherever used. In standard sizes—12" x 12" (in lengths 15 ft. to 40 ft.) and 14" x 14" (lengths 15 ft. to 55 ft.). Other sizes made to order.

Write for full details



STENT PRECAST CONCRETE LTD

Chequers Lane, Dagenham Dock, Essex. DDN 0971 (4 lines)

Best Quality CONCRETE AGGREGATES in all grades

DELIVERED BY ROAD OR RAIL

**WM. BOYER
& SONS LTD**

MEMBERS OF S. & G.A. of G.B.

ESTABLISHED 1818

IRONGATE WHARF, PADDINGTON, W.2

TELEPHONE : PADDINGTON 2024-4

SCHMIDT



CONCRETE TEST HAMMER

for immediate non-destructive
determination of compressive
strength

O. A. VOLKMANN LTD

3 ST. AUGUSTINE'S ROAD,
BIRMINGHAM, 16

Telephone: Edgbaston 1353

CONCRETE IN SULPHATE- LADEN SOILS

To eliminate risk
CIMENT FONDU
SHOULD BE USED

To ensure
complete protection
CIMENT FONDU
MUST BE USED

Concrete
made with
CIMENT FONDU is
COMPLETELY IMMUNE
from the effects of
SULPHATES
In any concentration

Concrete made with Ciment Fondu provides an additional margin of safety! It is also resistant to attack by dilute acids often prevalent in sulphate-bearing clays, made-up ground and many industrial effluents.



**Send for leaflet TSS-16 "The Influence of Mineral Sulphates on the Permanence of Concrete Structures."*

LAFARGE ALUMINOUS CEMENT COMPANY LTD., 73 Brook St., London, W.1. Tel: MAY 8848

4P/80



**PUT YOUR FAITH
IN THE TESTED
BRAND**

THIS LABEL ON
EVERY BARREL
CARRIES WITH
IT FIFTY YEARS'
EXPERIENCE OF
MANUFACTURE.

**NONE OTHER IS
"JUST AS GOOD"**

THE LEEDS OIL & GREASE CO.

Phone 22480

LEEDS, 10 'Grams: "Grease, Leeds 10"



42" diameter to 27"
diameter straight
back mould for
manhole tapers.

Moulds and formwork

for the concrete industry

A service to the industry ranging
from the small equipment illustrated
to complete spinning plants, backed
by years of technical experience.


We are now operating from our ex-
tensive new premises at the address
below.

Further details and quotations sent on request

Coneybeare

THE ORIGINAL PIPE MOULDS

Coneybeare & Co. Ltd., Torrington Road, Ashford, Kent. Tel: Ashford 1545/6



CONCRETE ROADS FIRST because CONCRETE ROADS LAST

REINFORCEMENT
by McCALLS

'Masolar' road mesh at Long Nook, Birmingham

McCALL & COMPANY (SHEFFIELD) LIMITED

TEMPLEBOROUGH • SHEFFIELD • P.O. BOX 41

Telephone: ROTHERHAM 2076 (P.B. Ex. 8 lines)

LONDON: SLOANE 0428

BIRMINGHAM: ACOCKS GREEN 0229

PORTSMOUTH: COSHAM 78702

MANCHESTER: BLACKFRIARS 1018

McCALLS MACALLOY AFRICA (PROPRIETARY) LIMITED

McCALLS MACALLOY (AUSTRALIA) PTY. LIMITED

500-41

McCALL & COMPANY (SHEFFIELD) LIMITED

McCALLS MACALLOY LIMITED

McCALLS MACALLOY (CANADA) LIMITED

'PUDLO' PROVIDES PROOF . . . No. 3 OF A SERIES

Underground story... of Waterproofed Ready-Mixed Concrete

When, in 1958, the beer cellar of the 'Harp' public house at Parson's Mead, Croydon, was excavated for rebuilding, water was found to be present at a depth of only 3 ft. 6 in. below the level of the upper surface of the old floor. To combat these inherently damp conditions 'Pudlo' CEMENT WATERPROOFING POWDER was specified for the READY-MIXED CONCRETE used in the new floor.

'Pudlo Waterproofer' was also used in the internal rendering of the outer walls and, to ensure complete protection from damp penetration, a 'Pudloed' cove was formed at the junction of the wall and floor.

TECHNICALITIES:

Floor Area: approximately 1,350 square feet.
Composition: Waterproof Ready-Mixed concrete to 8" thick, with granolithic surface.


Mix: 4 : 2 : 1 reinforced with No. 8 B.R.C. fabric and waterproofed with 14 lb. 'Pudlo' cement waterproofer per cubic yard of 'SURECRETE' Ready-Mixed Concrete.

Walls: Hard semi-engineering brick, to a thickness of 13½ inches.

Internal Rendering

Two parts Westorham Sand. One part Portland Cement. 5 lb. 'Pudlo' to every 100 lb. cement, applied in three coats to a minimum thickness of one inch.

Beer Cellar of the 'HARP', Parson's Mead, Croydon. By courtesy of Page and Overton's Brewery Ltd.



'PUDLO'

CEMENT WATERPROOFING POWDER

Architects:
Leonard Chignall & Son,
F.I.A.A., M.INST.R.A.,
M.R.S.A.N.I., Romford.

Contractors:
Galbraith Bros., Croydon.

Sole Proprietors and Manufacturers:

KERNER-GREENWOOD & CO. LTD.,


KING'S LYNN,

NORFOLK

Telephone: King's Lynn 2293

other 'PUDLO' products include: Waterproof Cement Paints, Cement Paint Primer, Cement Bonder, External Water Repellent, Plaster Bonder, Frost Protector/Rapid Hardener, Concrete Plasticiser, Mortar Plasticiser, Cement Hardener/Dust Proofer, Permanent Colours for Cement, 'Fausol' Fire Cement.

MILLIONS OF TONS OF TRAFFIC



WILL PASS OVER THIS BEAM

When finished, the spectacular $\frac{1}{2}$ -mile long Hammersmith Fly-over will contain 204 mammoth concrete beam segments weighing from 35 to 60 tons. These, together with a similar number of cantilever units of some 15 tons each, form the spine beam and ribs of this structure when jointed together and stressed. All have been cast by the contractors, Marples, Ridgway and Partners at their Heston casting yard, who selected Winget Vibrocon Poker Vibrators for the compaction of the high-grade dense concrete within the intricate moulds and complex reinforcements.

For maximum compaction use Winget 'Vibrocon' Poker Vibrators—the finest available today!

Client:
The London County Council

Consulting Engineers:
G. Maunsell & Partners
in association with
J. Rawlinson CBE., M.Eng.,
Chief Engineer LCC

Contractors:
Marples, Ridgway
& Partners Ltd.



Winget

LIMITED, ROCHESTER, KENT TELEPHONE STROOD KENT 72041 (8 LINES)

LENSCRETE LTD

maximum light minimum cost


LITEX roof lights give a very high transmission of light—up to 92%—and are easily and quickly handled and fitted. A full range of standard form metal ventilators, curbs and liners are available for use with LITEX roof lights.

**LITEX spherical roof lights**


*Lite*x

**LAMINATED FIBREGLASS
roof lights**

LITEX roof lights with their glass fibre reinforced construction can be used with advantage in many places where conventional lights would be impracticable or too costly. Virtually unbreakable, heavy packing is unnecessary allowing quick and easy handling on site.

**LITEX rectangular roof lights**

LITEX roof lights are ideal for use in schools, hospitals and other buildings where absolute safety is required—they will not shatter and cannot support combustion. The plastic will not creep, nor become brittle with age or very hot temperatures.



LITEX roof lights are not attacked by smoke or fumes from most industrial processes, and may safely be used in factory and workshop buildings.

For further information about LITEX roof lights please write to

LITEX lantern lights

LENSCRETE LIMITED Queens Circus London SW8 telephone MACaulay 1063

Ensure
safety
with

DORMAN LONG Steel Trench Sheet

(Regd. Design No. 830,839)

The ideal for temporary lining,
easy to drive: can be used over and over again

PROMPT DELIVERY Prices and full particulars on application to

DORMAN LONG (Steel) LTD., SHEET DEPT., AYRTON WORKS, MIDDLESBROUGH
London Office: Terminal House, 52 Grosvenor Gardens, S.W.1



**FOR THE LONG HAUL
RELY
ON**

PLAZCRETE

THE MODERN AID FOR A WELL-DESIGNED CEMENT MIX

PLAZCRETE RETARDS THE SET

Permits longer haulage time
Avoids day joint problems

PLAZCRETE IMPROVES WORKABILITY AND PLASTICITY

Makes pumping easier
Saves time placing and vibrating
Improves consolidation, particularly around reinforcement

PLAZCRETE PERMITS A REDUCED WATER/ CEMENT RATIO

Reduces shrinkage
Eliminates laitence, bleeding and segregation

PLAZCRETE IN THE MIX REDUCES THE COST WITHOUT ANY LOSS OF STRENGTH

For further information write to Dept. FC.:

SEALOCRETE PRODUCTS LTD.,
ATLANTIC WORKS, HYTHE ROAD,
LONDON, N.W.10.

Telephones: *Ladbroke 0015, P.B.E.*
Telegrams: *Sealocrete, Wexphone, London.*

N.B. When retarding of the set is not required Plazcrete (Non-retarding) can be supplied.





LILLINGTON'S NO. 1

Metallic liquid

smooths the way for
ATCO mowers

The new ATCO Service Branch at Marsh Barton, Exeter, is one of a chain spanning the country where anything from a quick service job on site or a major workshop overhaul can be tackled.

To render the concrete floors hard, waterproof, dust-free and able to withstand exceptionally heavy wear and tear, Lillington's No. 1 Metallic Liquid was the natural choice.

For fifty years architects have specified No. 1 Metallic Liquid, as the scientifically prepared admixture that makes concrete completely waterproof and dustless, as well as accelerating the setting time. No. 1 Metallic Liquid is a necessity for waterproofing cement renderings to walls and basements, mass concrete retaining walls, foundations, flat roofs and tanks. You can rely on Lillington's No. 1 Metallic Liquid to give complete satisfaction because IT IS THE ONLY PROOFER SOLD UNDER GUARANTEE.

FROM

5'.

PER GALLON

Special terms for
bulk contracts

Write for Booklet 56

LILLINGTON'S

No. 1 Metallic Liquid

GEORGE LILLINGTON AND COMPANY LIMITED


Willow Lane, Mitcham, Surrey. Tel: Mitcham 1066 For Scotland: 42 High Street, Greenock

ALL OUR PRODUCTS ARE SUPPLIED IN FREE CONTAINERS

AP 369

AB MOULDS

**CAN BE RELIED UPON TO
GIVE CONSISTENT SERVICE
OVER MANY YEARS**



The above illustration of a standard garden edging mould shows the tough construction of our moulds, which reduces expenditure on maintenance and constant replacement of moulds of less robust design.

A. B. MOULD & CONSTRUCTION CO., LTD.

**VULCAN WORKS, VULCAN WAY
NEW ADDINGTON, SURREY**

Telephone : Lodge Hill 2347

Telegrams : Abmould, Croydon

GUNITE SPECIALISTS

**W.M. MULCASTER
& CO. (CONTRACTORS) LTD.**

We invite inquiries for Gunite Linings and Renderings
for new or old structures of every kind in any part
of the country.

HASLINGTON

CREWE

Telephone : Crewe 2265-6



BOLTS & NUTS

TIE-RODS ETC.


**FOR THE
CONTRACTOR**



Manufactured by

B. PRIEST & SONS LTD · OLD HILL · STAFFS · ENG

Telephone: Cradley Heath 66501 (8 lines)



Tel.: UXBRIDGE
33399

T.P.S. SHUTTERING and MOULD PAINTS

will make your shuttering and moulds last longer,
often save the labour costs of repeated mould oil
application, and are also the cheapest alkali
primers for general use under paint work

*Reduced costs and clean concrete surfaces are always obtained from shutters and
moulds treated with these paints. Wood grain is filled and sealed against water and
alkali. Douglas Fir staining eliminated*

Ask for the type for YOUR purpose
SPECIAL TYPES FOR PLYWOOD,
STEEL OR CONCRETE SURFACES
TO SUIT ALL REQUIREMENTS

PROMPT DELIVERY FROM STOCK!

TECHNICAL PAINT SERVICES, DEPT. C.C.E.
THE PAINT CENTRE — UXBRIDGE — MIDDLESEX



REINFORCEMENT SERVICE *including* SUPPLY & BENDING

We are manufacturers of mild steel bars for reinforced concrete, and have every facility for supplying bars cut to required lengths. We also bend ready for fixing if desired for contracts in any part of the country. Include our name on your list for future reinforcement requirements.

WALKER WRIGHT & CO. LTD

DARNALL, SHEFFIELD, 9

TELEPHONE: 41063-4-5



**Precast
REINFORCED
CONCRETE
frames**



* Industrial buildings designed, supplied and erected by

STUARTS
GRANOLITHIC CO. LIMITED


ESTABLISHED 1940

REINFORCED CONCRETE
INDUSTRIAL FLOORS
RECONSTRUCTED STONE

LONDON ADDRESS: 14 College Road, Harrow. Tel: Harrow 8181-3-3

BIRMINGHAM: Northcote Road, Stochford. Stochford 3831-2. EXETER: 6-8 Melbourn Street, Exeter 12668.
EDINBURGH: 48 Duff Street, Don 1281-8. MANCHESTER: Ashton Road, Bradbury, Stockport. Woodley 5871-4.

*a proven material
with a **BIG IMPACT**
on design*




FILIGREE by **HEAD WRIGHTSON**

For fast low cost floor construction the patented filigree welded steel joist offers many advantages.

Produced automatically, supplies are available at short notice, and the light weight of this strong reinforcement girder facilitates transport to site.

Designed for use with hollow block, hollow tile and cast in situ floors, filigree offers

- ★ A light but strong girder of consistently high quality.
- ★ Speedier and easier construction.
- ★ Availability in three depths.



We should welcome a visit from you, but if you cannot arrange this, please write or phone for more information to

the Sales Manager **FILIGREE DIVISION**

HEAD WRIGHTSON TEESDALE LTD

TEESDALE IRON WORKS • THORNABY-ON-TEES • TEL: STOCKTON 62241



GLASS FIBRE *and the* FORMWORK DESIGNER

There is almost an unlimited scope in the design of formwork if glass fibre is used. Our wide experience in the use of this material in concrete work—which is second to none—is always available on all formwork problems.



D. A. MODELS LTD

108 WOODSTOCK ROAD, LONDON, W.4

Telephone: CHiswick 2011

TODAY'S MOST ACCURATE, SPEEDY AND ECONOMICAL SYSTEM OF CONCRETE PREPARATION



Ground-level aggregate weighing & batching plants

**1 "ON THE JOB" AGGREGATE STOCKPILING,
CONTINUOUS HANDS-ON FEEDING**
... 100 compartments for 3 to 5 aggregates

2 REMOTE CONTROL OPERATION
... One man operated lever system

3 ACCURATE WEIGHING
... Clear view weigh dial

**4 DIRECT FEEDING OF CEMENT
INTO MIXER PAN**
... high-angle cement screw weigher

5 HIGH-OUTPUT, QUALITY CONCRETE
... Post-tensioned "Wynmar" mixer

6 CONCRETE STORAGE
... remotely controlled hopper



Photograph taken by
kind permission of
TERSONS LIMITED

A.C.E. MACHINERY LIMITED · PORDEN ROAD · BRIXTON · LONDON · S.W.2

Telephone: BRIXTON 3293 (9 lines). Telegrams: Auscon Telex 23579 LONDON



Circular tipping skips 1½ cu. ft. to 3 cu. yd.

ABELSON for SKIPS



Special and non-standard skips manufactured to your specifications



Circular controlled discharge bottom dump skips ½ cu. yd. to 1 cu. yd.

Rollover skips ½ cu. yd. capacity.



Concrete pouring skip skip discharge 10 cu. ft. to 27 cu. ft.



Flat skips 3 cu. ft. to 7 cu. ft.



Square tunnelling or trenching skips 4-60 cu. ft. capacity.



Concrete pouring skips bottom discharge 10 cu. ft. to 27 cu. ft.

WE ARE SPECIALISTS ★ **WATERTIGHT LININGS FOR RESERVOIRS**
IN THE REPAIR ★ **SWIMMING POOLS, ETC.**
AND RECONDITIONING ★
OF REINFORCED ★ **LININGS FOR TUNNELS**
CONCRETE STRUCTURES ★ **SEWERS**
★ **TANKS, ETC.**

GUNITE

CONSTRUCTION CO LTD

WESTERN HOUSE, HITCHIN, HERTS.

TELEGRAMS:
'GUNITE,
HITCHIN'


TELEPHONE:
HITCHIN 4371

WESTWOODS

HI-LOAD BRIDGE BEARING

TAKES 600 TON LOAD

4" DIA. ROLLER, 24" LONG



Rolling parts made from steel to a special specification. Precision workmanship. A very compact roller bearing for heavy reaction. Completely enclosed in grease box. No maintenance required. Bearings designed to suit all loads and conditions.

Apply for further details:

JOSEPH WESTWOOD & CO LTD
NAPIER YARD MILLWALL LONDON E 14

Phone: EASt 1043

Cables: Westwood London

Grams: Westwood Easphone London

E

INSEPARABLE from REINFORCEMENT



... OF COURSE!

**and a guarantee that
the specified concrete cover
is accurately maintained . . .**

Complying in ALL respects to the British Standard & Codes of Practice. The U-KLIPON BAR SPACER of revolutionary design is instantly fixed with a vice-like grip in the desired position on all types of reinforcement, including mesh and prefabricated. As an inseparable part it positively cannot be displaced by heavy tamping or vibrating. For any Bar Spacing problem,

CONSULT

THE B.E.C. BAR SPACER SERVICE

which has been and is responsible for the most outstanding and prominent contribution to accurate bar spacing in reinforced concrete, thus providing precision, economy, and labour-saving means of ensuring that the specified concrete "cover" is maintained under all conditions. It is noteworthy that such is the increasing popularity and demand for "B.E.C." Bar Spacers, borne out by sales in excess of 35 millions, that we are able to RETAIN OUR PRICE LIST OF 1945 WITHOUT MODIFICATION. Over 120 stock sizes of bar spacers enable us to give immediate attention to requirements. Write now for comprehensive details and samples. Our Technical Consultants will call on request.

Patent Nos. 597,505, 715,563, 789,018, 818,538.

Registered Nos. 870,560, 886,239. English and foreign patents pending.



B.E.C. BEARER BLOCK

**FOR GROUND BEAMS • BARREL ROOFING
BRIDGES • MAT WORK • ETC.**

The "B.E.C." precision-made bearer block is another inexpensive B.E.C. aid to obtain accuracy with speed in concrete construction. Let us send you full details.

BERRY'S ENGINEERING CO.

SOLE MANUFACTURERS:

Middle Road, Shoreham-by-Sea, Sussex

Phone and Grams: Shoreham-by-Sea 3541-2

CONTRACTORS TO MINISTRY OF SUPPLY, ETC., ETC.

Enhance your Prestige.
Specify and use with
confidence.

Testing concrete cubes on site

MILBANK-WELLS


HYDRAULIC PRESS AND CUBE MOULDS

Immediate Delivery

Two Sizes: 4 in. and 6 in.

PRESSES and CUBE MOULDS

Testing to 16,000 lb. per sq. in. to
B.S. 1881.



Approved for
all Government
Contracts

IN USE
ALL OVER
THE WORLD

6-IN. PRESS
258 TONS

4-IN. PRESS
110 TONS

MILBANK FLOORS LTD

PRESTRESSED CONCRETE CONSTRUCTION

RIVER HOUSE, EARLS COLNE, ESSEX

Telephone: Earls Colne 410



PRESTRESSED FLOORS & ROOFS SPANS UP TO 40 ft
FRAME BUILDINGS ALL TYPES



SINGLE SPAN · MULTI SPAN · CANTILEVER

RANALAH

for

STEEL MOULDS



Phone

BRIGHTON 62216-7-8-9

for IMMEDIATE ACTION

RANALAH STEEL MOULDS LTD
LOWER BEVENDEAN • BRIGHTON • SUSSEX

ALLAM

TRILLOR ELECTRIC EXTERNAL VIBRATORS



**specially designed
for very dry mixes
for in situ and
precast concrete**

This High Frequency Vibrator is available in eight sizes, most of which are equipped with quick-release attachment fittings, which enable them to be used with the highest vibrating efficiency for all types of steel and wooden shuttering and moulds. If required, surface plates or pans can be fitted for surface vibration



E · P · ALLAM & CO. LTD.**LONDON : 132-135 Sloane Street, S.W.1. • Telephone: Sloane 9976 (5 lines)****Works: Southend-on-Sea Tel.: 525243**

AGENTS & DISTRIBUTORS: Strangford Ltd., Belfast and Dublin; A. Gunn & Co. Ltd., Altrincham, Ches.; O. L. Davies, Ltd., Port Talbot, Glam.; J. Lewis (Machinery) Ltd., Burslem, Stoke-on-Trent; Concrete Engineering Services, York Road Industrial Estate, Wetherby, Yorks; John Houlstone Ltd., Newcastle-on-Tyne; W. R. Salwood Ltd., Chandler's Ford, Southampton; J. A. McAra & Co. Ltd., Glasgow; Modern Plant Sales Ltd., Oldbury, Birmingham; Ernest Doe & Son Ltd., Industrial Division, Ulling, Maldon, Essex; Contractors Plant (Notts.) Ltd., 78 Nottingham Road, Stapleford, Nottingham.

The Portakabin

a
major
advance
in
site
accommodation
standards

Designed for use
in single or
multiple units
Provides a full range
of office and canteen
accommodation



PORTABILITY—

Rapid loading and off-loading by one man.

AVAILABILITY—

Ready for immediate occupation.

STACKABILITY—

Can be stacked up to three high.

Covered by Patent applications

PORTAKABIN LTD. Home Sales Office
LAWRENCE ROAD GREEN LANE HOUNSLOW MIDDLESEX Telephone HOUNSLOW 4622
Head Office YORK and at BIRMINGHAM MANCHESTER GLASGOW BRISTOL BELFAST DUBLIN

CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

Volume LVI, No. 9.

LONDON, SEPTEMBER, 1961.

EDITORIAL NOTES

Earthquake-resistant Construction.

DURING the past two or three decades there has been considerable development in the theory and practice of designing structures to resist the effects of earthquakes. At one time, the simplicity of the method was such that a building was designed to resist a horizontal force equal in magnitude to, say, one tenth its own weight or of the dead weight of that part of the structure above any horizontal plane being considered. The complexity of the subject today is seen from the contents of the papers presented at the Second World Conference on Earthquake Engineering, which was held last year in Tokyo and elsewhere in Japan. The proceedings* of the Conference were published recently in the form of three volumes containing upwards of two thousand pages and a supplementary volume giving without comment the regulations applying to earthquake-resistant construction in about a dozen countries.

Some regulations, such as those of New Zealand, Portugal, Italy and Austria, are comparatively brief and specify a simple coefficient to be applied to the weight of the structure. Others such as those of France, California and Turkey are more elaborate in the assessment of the horizontal force; some countries including Canada and Venezuela adopt the U.S.A. formula. Other regulations, the Greek for instance, give a wealth of structural details. Probably the most complex and comprehensive are the Japanese regulations as might be expected in view of the fact that Japan has suffered much from severe earthquakes. The numerous factors which it is necessary to take into account include the weight and height of the structure, part of the live load, the probability of a snow load, the nature of the soil, the locality, and the material and nature of the construction; basic coefficients up to 0.3 or greater (compared with the common factor of 0.1) are applicable to some structures in certain districts.

The principal subjects dealt with in the hundred and twenty-four papers

* "Proceedings of the Second World Conference on Earthquake Engineering." Three volumes (and a supplementary volume). Price 17.00 U.S.A. dollars. Obtainable from Association for Science Documents Information, Institute of Technology, Tokyo, Japan.

presented at the Conference include soils and foundations, structural response, ground movements, earthquake-resistant design, and recent earthquakes. One of the primary conclusions is that theoretical study of the effects of earthquakes is valueless unless well supported by practical data. Examination of damage immediately after an occurrence is more rewarding than theoretical and experimental investigations. Earth movements due to seismic effects in the U.S.A. have been recorded in great detail and the records have been used effectively in research connected with earthquake-resistant structures. The influence of the type of ground on these effects is now well established but research dealing with the vibrational characteristics of soils continues, and the opinion was expressed at the Conference that this aspect of the problem deserves attention equal to that given to the more popular problem of structural response. In Japan, instruments have been installed in various parts of many buildings and some correlation between the behaviour of buildings and the type of soil is being obtained. During a severe earthquake, the material in many structures is likely to be stressed beyond the limit of elasticity. Some structures resist severe seismic effects because of plastic deformation. Therefore many papers dealt with the elasto-plastic response of structures and it was concluded that the development of a method of design based on the limitation of deformation is foreseeable. Another method of design that is claimed to be new is based on energy absorption.

Accounts of many recent earthquakes are given in the Proceedings and the effects on buildings, dams and other structures are described in sufficient detail to be of use in determining means of resisting seismic effects. The earthquake at Agadir in 1960, although disastrous, was not among the most violent shocks on record and, from a technical point of view as well as on humane grounds, this circumstance was fortunate because it allowed the most resistant buildings to survive and others less resistant to suffer damage roughly inversely to their resistance, thereby enabling the strong and weak points of modern construction to be examined.

New developments produce new problems. Damage of a nuclear reactor by earthquakes could lead to uncontrolled nuclear fission with the possibility of explosion and release of fission products, with consequent hazard to human life. Therefore these structures, such as that currently being constructed in Japan, are designed for the most severe seismic conditions and the detailed analysis must be more thorough than for structures of other types. It is worth while to draw attention to a method of building construction in Japan that has a high degree of resistance to seismic effects. In this method a framework of light lattice steelwork is erected first and is encased in reinforced concrete (not merely concrete with a minimum of encasement reinforcement). The resistance of such composite construction is considered to be the sum of the separate resistances of the steelwork and the reinforced concrete.

Although designers of structures to be erected in this country do not take seismic effects into account, the British Isles are not entirely free from natural seismic phenomena, although these are by no means so disastrous as those occurring in parts of the world well known for the severity of earthquakes. There are actually over a thousand authoritative records of earth tremors in Great Britain and many more of dubious authenticity. The vast majority of these occurrences were slight but some were sufficiently severe to cause structural

damage, and, in a few instances, fatalities. The year 1750 was known as the "earthquake year", and since then tremors, sufficiently severe to cause cracks in buildings and chimneys to fall from house-tops, have been centred at Inverness (in 1769, 1816 and 1901), Derbyshire (in 1795), Comrie, Scotland (in 1839 and 1841), Hereford (in 1863 and 1896) and Swansea (1906). Few parts of the country, including London, have been entirely free of slight tremors at some time during this period. The most severe earthquake in this country was in 1884 when more than a thousand buildings in and around Colchester suffered damage, a peculiarity being that the tremors occurred in a district that had hitherto been free from disturbances. Most other occurrences are associated with geological faults and it would appear that, even in this seemingly tranquil land, seismic disturbances in the vicinity of such faults are not unlikely. Ground shocks arising from intentional or accidental explosions may resemble natural seismic effects and to this extent a knowledge of earthquake-resistant construction is useful, but such knowledge is imperative if designers are concerned, as nowadays so many in this country are, with structures that are to be built in parts of the world where earthquakes of various degrees of severity are not only likely occurrences but are highly probable.

Responsibility for Constructional Costs.

WITH reference to the Editorial Note on "Structural Safety" in this journal for July last, and in particular with reference to the responsibility of constructors under French law, a reader sends the following extract concerning the financial obligations of architects, a term inclusive of structural engineers in the far-off days to which the extract applies.

"In the renowned and spacious Greek city of Ephesus, a law is said to have been made of old by the forefathers of the citizens, in harsh terms but not unjust. For when an architect undertakes the erection of a public work, he estimates at what cost it will be done. The estimate is furnished, and his property is assigned to the magistrate until the work is finished. On completion, when the cost answers to the contract, he is rewarded by a decree in his honour. If not more than a fourth part has to be added to the estimate, the state pays it and the architect is not mulcted. But if more than a fourth extra is spent in carrying out the work, the additional sum is exacted from the architect's property.

Would that the Gods had impelled the Roman people to make such a law not only for public, but also for private buildings! In that case unqualified persons would not swagger abroad with impunity, but persons trained in entirely accurate methods would profess architecture with confidence. Nor would owners be led on to unlimited and lavish expenditure, so that they are even dispossessed of their property; and the architects themselves, controlled by the fear of a penalty, would be more careful in calculating and declaring the amount of the cost. In this way the owners would finish their buildings to the sum provided or with the addition of a little more. For those who can provide 400,000 sesterces, and have to add 100,000 are content to be so bound, in the hope of completing the work while those who are burdened with the addition of a half, or more of the expense, lose hope, and declining further expenditure are forced to give up with broken fortune and spirit."—[From VITRUVIUS ON ARCHITECTURE (Vol. II).—The Loeb Classical Library. Translator: Frank Granger.]




Fig. 1.

See facing page.

The Analysis of Three-bay Frames by the Plastic-hinge Method.

By K. POOLOGASUNDRAM, Ph.D., A.M.I.C.E.

IN an article in this journal in February 1959⁽¹⁾, expressions are developed for the application of the theory of plastic hinges⁽²⁾ to a multiple-storey frame of three bays (Fig. 1) the ratio of the central span to the equal outer spans being variable. The object of the present article is to present suitable curves, based on these expressions, to enable the analysis of such frames to be speedily carried out. Expressions such as equations II in the previous article, suitable for graphical representation, can be derived by adopting the following assumptions and limiting values.

(1).—The length of each end span is L ; the length of the shorter central span is kL . The moments of inertia I of all beams are uniform; the moments of inertia J of all columns in the same storey are also uniform. Therefore

$$y = \frac{Ih_r}{JL} \quad \text{Also} \quad \frac{h_{r-1}}{J_{r-1}} = \frac{sh_r}{J_r}; \text{ the limits of } s \text{ are } 0.66 \text{ and } 1.$$

(2).—Vertical load on all beams may be either uniformly distributed or concentrated at the third-points. The maximum ordinate of the free bending-moment diagram in both of the end spans is M_1 , and in the central span is M_2 .

(3).—Values of m and \bar{X} in the $(r+1)^{\text{th}}$ storey with regard to the terms containing m are a times the values for the r^{th} storey; the limits of a are 0.75 and 1.0.

(4).—Values of m and \bar{X} in the $(r-1)^{\text{th}}$ storey with regard to the terms containing m are b times the values for the r^{th} storey; the limits of b are 1.25 and 1.0.

Values of Plastic-hinge Moments.

The limiting values for the plastic-hinge moments are given in formula (1), but differ slightly from those given in the previous article and are based upon research carried out by the author at Imperial College, London⁽³⁾.

$$\left. \begin{aligned} \bar{X}_{1rb} &= \bar{X}_{2rb} = 0.13m + 0.5M_1, & \bar{X}_{2rb} &= 0.22m + \frac{1.2M_1}{2+y} \\ \bar{X}_{2re} &= \bar{X}_{2rs} = 0.13m, & \bar{X}_{2re} &= \bar{X}_{2rs} = 0.13m - \frac{0.02M_1}{2+y} \\ \bar{X}_{1re} &= 0.10m - \frac{0.5M_1}{2+y}, & \bar{X}_{4re} &= 0.10m + \frac{0.5M_1}{2+y} \end{aligned} \right\} \quad (1)$$

1. E. W. TOKARSKI.—"Application of the Plastic-hinge Method to a Multiple-storey Frame." "Concrete and Constructional Engineering", February 1959.

ERRATA.—In Table I in this article the value of the influence of \bar{X}_{2re} on θ_{2re} should be $-\frac{1}{2}(2+2a+y)$ and the value of the influence of \bar{X}_{4re} on θ_{4re} should be $-\frac{1}{2}(2(a+b-2)+y[2b+a-4(1+s)])$.—ED.

2. A. L. L. BAKER.—"The Ultimate Load Theory Applied to the Design of Reinforced and Prestressed Concrete Frames." 1956.
3. K. POOLOGASUNDRAM.—"An Analytical and Experimental Investigation of the Formation and Behaviour of Plastic Hinges in Prestressed and Reinforced Concrete Frames." University of London, Ph.D. Thesis, 1959.




Chart No. 3.

Chart No. 2.

Substituting these plastic-hinge moments in equations II and expressing the ratio $\frac{M_2}{M_1}$ as r_M and the ratio $\frac{m}{M_1}$ as r_m , formulae (2) are obtained.

$$\left. \begin{aligned} \theta_{1rb} &= \frac{M_1 L}{EI} \left[\frac{0.167y - 0.25ky - 0.5k + 0.140}{2+y} + 0.333kr_M + 0.021kr_m \right] \\ \theta_{2rb} &= \frac{M_1 L}{EI} \left[\frac{0.167y - 0.25ky - 0.5k + 0.12}{2+y} + 0.333kr_M \right. \\ &\quad \left. + (0.0067 - 0.021k)r_m \right] \\ \theta_{3rb} &= \frac{M_1 L}{EI} \left[\frac{0.213y + 0.206}{2+y} + (0.013y + 0.013)r_m \right] \\ \theta_{2ra} &= \frac{M_1 L}{EI} \left[\frac{0.113y + 0.25ky + 0.5k + 0.113}{2+y} - 0.333kr_M \right. \\ &\quad \left. + (0.015y - 0.021k + 0.065)r_m \right] \\ \theta_{3ra} &= \frac{M_1 L}{EI} \left[\frac{-0.05y - 0.007}{2+y} + (0.015y + 0.058)r_m \right] \\ \theta_{1rc} &= \frac{M_1 L}{EI} \left[\frac{-0.08y}{2+y} + 0.03yr_m \right] \\ \theta_{2rc} &= \frac{M_1 L}{EI} \left[\frac{0.113y + 0.25ky + 0.5k + 0.113}{2+y} - 0.333kr_M \right. \\ &\quad \left. + (0.015y - 0.022k + 0.065)r_m \right] \\ \theta_{3rc} &= \frac{M_1 L}{EI} \left[\frac{-0.05y - 0.007}{2+y} + (0.015y + 0.059)r_m \right] \\ \theta_{4rc} &= \frac{M_1 L}{EI} \left[\frac{0.1y}{2+y} + 0.01yr_m \right] \end{aligned} \right\} \quad (2)$$

Design Charts.

The general form of all the foregoing expressions is

$$\theta = \frac{M_1 L}{EI} [Y_{M1} + Y_{M2}r_M + Y_mr_m],$$

where Y_{M1} , Y_{M2} and Y_m are functions of y for a given value of k . The charts accompanying this article give the values of these functions plotted against values of y from 0 to 12. Separate charts are given for values of k of 0.2, 0.4, 0.6, 0.8 and 1.0. Using these charts it is possible to calculate the rotations of the hinges easily and quickly as r_M and r_m are known quantities.

The object of the calculations is to make the rotations positive and to keep them within the permissible values. If the rotations obtained by using the curves are negative or are greater than the permissible values, the bending moment diagrams can be adjusted at certain sections, still keeping the adjusted moments in equilibrium. The additional rotations can be determined by applying the influence coefficients given in Table I in the previous article⁽¹⁾.

EXAMPLE.—To determine the rotations of the hinges of an intermediate storey of a three-bay frame having the stated dimensions and subjected to the bending moments specified.




Chart No. 4.

Chart No. 5.

End spans $L = 20$ ft.; central span $kL = 10$ ft.; hence $k = 0.5$; storey-height $h = 12$ ft.

Free bending moments (at ultimate load):

On outer beams $M_1 = 6,000,000$ in.-lb.

On central beam $M_2 = 3,000,000$ in.-lb.

Free sway moment m due to wind = 2,000,000 in.-lb.

It is assumed that the values of a , b and s for the storeys above and below the storey considered are within the limits assumed in the charts. The crushing strength of works-cubes u_w at twenty-eight days is 4000 lb. per sq. in.; the equivalent elastic compressive stress in bending $c' = 0.5u_w = 2000$ lb. per sq. in.

Assume the maximum bending moment M' on an end span to be approximately $0.6 \times 6,000,000 = 3,600,000$ in.-lb. Since the section at which this bending moment occurs is within the elastic range, $I = \frac{M'n_1d}{c'}$ where n_1d is the depth to the neutral axis. Assume the columns to be 18 in. by 12 in., $d = 18$ in., and $n_1 = 0.33$.

$$\text{Then } I = \frac{3,600,000 \times 0.33 \times 18}{2000} = 10,700 \text{ in.}^4 \text{ and } J = \frac{12 \times 18^3}{12} = 5840 \text{ in.}^4$$

$$\text{Thus } \gamma = \frac{Ik}{JL} = \frac{10,700 \times 12}{5840 \times 20} = 1.1. \text{ If } E_c \text{ is approximately } 5000u_w,$$

$$E_c = 500 \times 4000 = 2 \times 10^6 \text{ lb. per sq. in.}$$

$$\text{Then } \frac{M_1L}{EI} = \frac{6,000,000 \times 20 \times 12}{2 \times 10^6 \times 10,700} = 0.067.$$

$$r_M = \frac{3,000,000}{6,000,000} = 0.5, \quad r_m = \frac{2,000,000}{6,000,000} = 0.33.$$

Interpolating between the charts for $k = 0.4$ and 0.6 , the values of Y_{M_1} , Y_{M_2} and Y_m are obtained for each hinge, for a value of γ of 1.1. The rotations of the hinges are computed in Table A.

TABLE A.

Hinge	Y_{M_1}	Y_{M_2}	Y_m	$\theta = \frac{M_1L}{EI}(Y_{M_1} + r_M Y_{M_2} + r_m Y_m)$	θ
1-r-b	-0.021	0.167	0.011	$0.067(-0.021 + 0.084 + 0.004)$	0.0045
2-r-b	-0.028	0.167	-0.004	$0.067(-0.028 + 0.084 - 0.001)$	0.0037
3-r-b	0.142	0	0.027	$0.067(0.142 + 0 + 0.009)$	0.0100
2-r-a	0.201	-0.167	0.071	$0.067(0.201 - 0.084 + 0.024)$	0.0094
3-r-a	-0.020	0	0.076	$0.067(-0.020 + 0 + 0.025)$	0.0003
1-r-c	-0.028	0	0.033	$0.067(-0.028 + 0 + 0.011)$	-0.0011
2-r-c	0.201	-0.167	0.071	$0.067(0.201 - 0.084 + 0.024)$	0.0094
3-r-c	-0.020	0	0.076	$0.067(-0.020 + 0 + 0.025)$	0.0003
4-r-c	0.035	0	0.011	$0.067(0.035 + 0 + 0.004)$	0.0027

It will be seen that the rotations of all the hinges are positive with the exception of 1-r-c. This rotation can be made positive by reducing the plastic moment of this section, but while so doing care must be taken to make any adjustments to the plastic moments at other sections which may be necessary in order to keep the distribution of bending moments in equilibrium with the applied loads.

Reduce X_{1rc} by $0.1 \frac{M_1}{2 + \gamma} = 0.032 M_1$ and, to maintain equilibrium, increase X_{4rc} by $0.032 M_1$ correspondingly. The resulting changes in the rotations may be determined by use of the influence coefficients in Table I⁽¹⁾. The additional rotations are


$\Delta\theta_{1rb} = \Delta\theta_{2rb} = 0$, $\Delta\theta_{3rb} = \Delta\theta_{1rc} = 0.0024$, $\Delta\theta_{2ra} = \Delta\theta_{3ra} = \Delta\theta_{3rc} = \Delta\theta_{3re} = 0.0012$ and $\Delta\theta_{4re} = -0.0024$.

Adding these hinge-rotations to those obtained in Table A, the final values of rotation at the plastic hinges are

$$\begin{array}{lll} \theta_{1rb} = 0.0045, & \theta_{2rb} = 0.0037, & \theta_{3rb} = 0.0124, \\ \theta_{2ra} = 0.0106, & \theta_{3ra} = 0.0015, & \theta_{1rc} = 0.0013, \\ \theta_{3rc} = 0.0106, & \theta_{3re} = 0.0015, & \theta_{4re} = 0.0003. \end{array}$$

All the rotations are now positive and are reasonably small. Expressions for the maximum permissible rotations have been developed by the writer after detailed research and additional information on the formation and behaviour of plastic hinges with different types of reinforcement, etc., is also available⁽²⁾.

An Architectural Congress.



THE accompanying illustration shows an ornamental wall at the enquiry desk at the Sixth Congress of the International Union of Architects, which was held in London in July last. The wall was 24 ft. long with an enclosure 4 ft. in diameter at each end, and 8 ft. 3 in. high. It was built of "Spectra-glaze" blocks of a standard colour called "decorative blue". The blocks are of concrete with the surface impregnated with thermo-setting resin.

As announced in the number of this journal for April 1961, the theme of the Congress was "New Techniques and

Materials—Their Impact on Architecture". Despite the subject, the wall illustrated, a similar structure at the book exhibition held in connection with the Congress, and some paving were the sole material representatives of the concrete industry. In the accompanying exhibition of photographs, however, concrete structures of many types predominated.

Included in the papers presented at the Congress was one by Pier Luigi Nervi entitled "Reinforced Concrete and Technical and Scientific Progress of the Architecture of Today and Tomorrow".

Concrete Construction at Trawsfynydd Nuclear Power Station.




FIG. 1.

THE civil engineering work at the 500-megawatt nuclear power station (*Fig. 1*) in the course of construction for the Central Electricity Generating Board at Trawsfynydd, North Wales, is now well advanced. The station is on a hilly site about 600 ft. above sea level and adjacent to Trawsfynydd Lake. The principal structures are the two reactor buildings

and the turbine house. The cooling-water pump house will contain six pumps which will be capable of circulating 500,000 gallons of water per minute, the water being drawn from the lake and returned thereto for cooling by natural means. A labour camp near the site has accommodation for about a thousand men.

The arrangement of the structures is




Fig. 2.




Fig. 3.

reasonably compact. There are three principal areas, namely the reactor area, fuel-disposal area, and turbine house area. Around the site there is a main access road, and therefore buildings requiring access from the public highway are located near this road so that there is no need for vehicles to enter the reactor or fuel-disposal areas.

Foundations.

The original site undulated by about 50 ft. and the quantity of excavation required to level the site and for the foundations was about 450,000 cu. yd. The ground is mainly rock, which is a silicious medium-grained greywacke in the Rhinog grit series of the Cambrian system. The rock was overlain in parts by a glacial moraine and much peat, both of which

materials contained boulders. The rock, however, is at convenient levels to enable most of the main foundations to bear on it; as a result there is no likelihood of differential settlement occurring between associated parts of the plant.

The foundations of the reactors comprise a raft and extend 25 ft. below the finished ground level of the site. The raft was cast in sections (Fig. 2). Thermocouples embedded in the base of the reactors were installed on precast pillars (Fig. 5) which were retained in place by a steel-angle frame as shown in the illustration.

The foundations for the rail-track for a 400-ton Goliath crane also bear on the rock which is in places 20 ft. below rail level. The concrete in this foundation was placed by pump.



Fig. 4.

Foundations for some of the temporary buildings, such as workshops, are on consolidated filling, but special foundations, such as those for test beds and furnaces, are taken down to undisturbed moraine.

Reactor Buildings.

Each reactor building, of which there are two, contains a reactor and six boilers (or heat-exchangers), and are each 298 ft. long, 180 ft. wide, and 179 ft. high, with a substructure extending 17 ft. 9 in. below the finished ground level. The buildings and shield-walls are of reinforced concrete,

except the roof frames, crane beams and parts of the boiler houses which are of steel. The cladding is mainly of precast concrete panels, but parts of the boiler houses are of cast-insitu concrete.

The biological shield-walls are 10 ft. to 10 ft. 6 in. thick and form a cylinder (Fig. 3) of 70 ft. diameter. Their height




Fig. 5.




Fig. 6.




Fig. 7.

is 93 ft. above the foundations. The top slab over the reactors will be 11 ft. 6 in. thick, and will comprise precast reinforced concrete beams combined with cast-insitu concrete. The inner face of the shield-wall will be cooled by air flowing in a cavity between twin steel plates, one of which forms permanent shuttering for the wall.

The boilers, which are 18 ft. in diameter and 108 ft. high, are supported on reinforced concrete frames carried on plinths 31 ft. above the ground. The reinforced concrete walls around the boilers are 100 ft. high and, for shielding purposes, are from 12 in. to 18 in. thick. The walls

are being built after the pipes connected to the boilers are installed.

The site of each reactor building is commanded by two mono-tower cranes (Fig. 4) which can travel on short lengths of parallel tracks, and can lift 5 tons at a radius of 100 ft.

Cooling Pond.

The pond for cooling irradiated fuel elements is parallel to the reactor buildings and is 335 ft. long, 35 ft. wide and 20 ft. deep. The fuel elements are passed to the pond through massive reinforced concrete chutes. The thickness of the bottom and walls of the pond is generally



Fig. 8.



Fig. 9.

about 3 ft. The shuttering for the walls (Figs. 6 and 7) comprises large timber panels, with plywood lining, some of which are 18 ft. by 7 ft. After each use the panels are repaired, if necessary, at the site of the pond. They are lifted by means of a mobile crane on endless tracks and, if required at the other end of the pond, are transferred thereto on a low-loader. The walls are constructed in lengths equal to that of the panels of shuttering and P.V.C. water-bars are inserted across the horizontal and vertical joints. The vertical joints ensure that shrinkage is taken up at predetermined

positions along straight lines with the edges of the joint suitably treated.

Turbine Hall.

The turbine hall will contain four turbo-generators arranged transversely. The main building, which is 370 ft. long, 140 ft. wide and 96 ft. high, is of steelwork, but the foundations, the plinths supporting the turbo-generators, the basement walls, circulating ducts, and some floors and roofs in the mechanical and electrical annex are of reinforced concrete. Fig. 8 shows the cast-insitu lower part of the walls in the course of construction. The




Fig. 10.



Fig. 11.

columns of the workshop attached to the turbine hall were precast on the site and were erected by excavators used as cranes (Fig. 9).

The cladding of the walls of the turbine hall and workshop are of precast exposed-aggregate slabs (Fig. 10), which are described in a subsequent paragraph.

Pump House.

The cooling-water pump house is a reinforced concrete structure extending 30 ft. below the normal level of Trawsfynydd Lake, on the shore of which it is situated. In plan, the structure is 250 ft. long and 110 ft. wide. Two mild steel pipes, about 10 ft. in diameter and encased in concrete, extend from the pump house to the turbine hall.

The outlet works are of reinforced concrete and are 80 ft. long; the width at the narrowest part is 42 ft., fanning out to 90 ft. Automatic safety gates, penstocks, and dam-boards are provided. The gates are intended to eliminate risk of flooding in the unlikely event of a break occurring in the discharge pipes.

Concrete.

The total amount of concrete in the works is about 200,000 cu. yd. Most of the concrete is made at a central batching and mixing plant (see Fig. 11 and on the right in Fig. 4) from which it is distributed in 14-cu. yd. tipping-hopper trucks to various parts of the site. For the turbine-hall basement, the pump house, the Goliath-track foundations, and some



Fig. 12.




Fig. 13.

other parts of the work, the trucks discharge the concrete into hoppers from which it is delivered to the point of deposit by concrete pumps. For the work at high levels on the reactors the concrete is transferred in skips by mono-tower cranes as seen in Fig. 4. The batching and mixing plant comprises two 1-cu. yd. drum-type mixers and has produced up to 2800 cu. yd. of concrete in a week. Most concrete is compacted by internal vibrators which are generally 4-in. high-frequency machines. Curing in dry weather is by means of saturated hessian.

The aggregates are stored in the open in radial compartments and are transported by a mobile shovel to the boot of the belt-conveyor (Fig. 12), which conveys the material to the storage bins of the batching plant. None of the rock on the

site has been used as aggregate mainly because, where it was of suitable quality, it occurred in pieces too large to be crushed economically. The coarse aggregate is generally uncrushed gravels obtained from glacial deposits in dry pits in Caernarvonshire and elsewhere. The sand is obtained from the same source by screening the detritus. Some oversize material is crushed.

Several grades of concrete are produced for various purposes. Ordinary structural concrete is specified to have a crushing strength of 5000 lb. per square inch at twenty-eight days. For the shield-walls and similar work, concrete having a guaranteed dry-density is required, the specified strength required being an average of 4250 lb. per square inch and not less than 3000 lb. per square inch;



Fig. 14.

the actual average strength of the concrete supplied is about 5000 lb. per square inch. With gap-graded rounded gravel aggregate, a dry density of 144 lb. per cubic foot is obtained with a water-cement ratio of 0.5. Stones of $\frac{1}{2}$ -in. size are omitted from the aggregate. In the concrete of guaranteed density, as also in mass concrete in the pump house which has to be watertight, pulverised-fuel ash obtained from the generating station at Bold, Lancs., is incorporated. About 800 tons of heavy concrete is to be made; this concrete is expected to have a density of about 360 lb. per cubic foot and will incorporate steel shot.

Finishes.

The general finish of the walls of the reactor buildings, the turbine hall, and some of the ancillary buildings comprises precast exposed-aggregate concrete slabs (Fig. 13) and are made in a factory installed on the site.

Some of the slabs are 25 ft. long and up to 8 ft. wide. The slabs are supported on corbels on the columns of the buildings, the method of attachment depending on whether the columns are of steel or of precast concrete as in Fig. 14. During erection, the slabs are drawn tightly against the supports by jigs attached to sockets embedded in the concrete. The face of the slabs is a crushed local grey granite, which is exposed by spraying with water and brushing with a soft broom while the concrete is still green.

The crushed stone is a mixture of Arenig granite and Pengwern and Gwydyr granites. The backing concrete is ordinary concrete of structural grade with $\frac{1}{2}$ -in. aggregate. In some of the buildings, the inner faces of the slabs are lined with wood-wool for thermal insulation purposes; the lining is embedded in the slabs at the time of manufacture. The wood-wool lining is seen in Fig. 14, which shows a view from the inside of a reactor building. [A description of the manufacture of the exposed-aggregate slabs is given in "Concrete Building and Concrete Products", August 1961.]

The finish to the reactor is fair-faced concrete as left by the shutters.

The designers and main contractors are Atomic Power Constructors Ltd., a consortium comprising Messrs. Crompton Parkinson Ltd., Fairey Aviation Ltd., Messrs. International Combustion (Holdings) Ltd., Messrs. Richardson Westgarth & Co. Ltd., and Nuclear Civil Constructors Ltd. The firm last named are the designers and contractors for the civil engineering work and comprise Messrs. Trollope and Colls Ltd., and Messrs. Holland & Hannen and Cubitts Ltd. The consulting architect to Nuclear Civil Constructors Ltd., is Sir Basil Spence and the consulting engineers are Messrs. Mott, Hay & Anderson. The sub-contractors include Pierhead Ltd., which firm supplied some prestressed precast slabs for floors in the turbine hall and prestressed beams for other buildings.

The Shearing Resistance of Beams by the Load-factor Method.


By C. ERDEI, B.Sc.Eng. (Hungary).

THE load-factor method is based on the principle that every part of a structure carrying a particular load should have the same factor of safety. The required factor of safety against shearing is not always achieved when the current methods of calculating shearing resistance are applied. Failure may occur before the calculated ultimate load is reached if the distribution of shearing reinforcement is unsatisfactory although the amount may be sufficient, or if the amount of main tension reinforcement is sufficient but if the bars do not extend beyond the position at which an inclined crack can start.


Notation and Definitions.

- b : Width of beam. d_1 : Effective depth of beam.
 δ : Original inclination of reinforcement to the axis of the beam.
 ω : Angle between the normal to a principal crack and the axis of the beam.
 α : Inclination of reinforcement after opening of crack.
 h : Horizontal projection of inclined crack.
 d_n : Depth of compression zone.
 Q, Q_c : Total shearing resistance, and shearing resistance of compressive zone respectively.
 M : Total bending resistance.
 Q_s : Force at failure in reinforcement provided to resist shearing.
 T : Force at failure in main tension reinforcement.
 f_s : Tensile strength of steel.
 p_{cb} : Safe compressive stress in concrete due to bending.
 p_{st} : Safe tensile stress in shear reinforcement.
 u_{cc} : Mean compressive bending stress in concrete at failure.
 u_{cb}, u_{cs} : Bearing and shearing strengths of concrete.
 $\beta = \frac{u_{cc}}{u_{cs}}, \gamma = \frac{\beta}{2b \cdot u_{cs}}.$
 A_{st} : Area of main tension reinforcement.
 A_{sv} : Area of stirrups.
 A_{si} : Area of inclined reinforcement.

The common assumption that the effects of shearing can be treated separately from those of bending has been shown to be incorrect. In reinforced concrete, as in homogeneous materials, the existence of stresses on two mutually perpendicular planes, caused by external loads, gives rise to principal stresses acting on principal planes. It has been shown that cracks due to shearing follow the directions of the principal stresses which would exist in a homogeneous material. These are here termed "principal cracks" (see Fig. 2a).



(a).—Equilibrium of forces.



(b).—Effect of cracking on principal stresses.

Fig. 1.




Fig. 2.—Cracking and Stresses at Failure.

After the occurrence of the principal cracks, a second system of cracks (here termed "secondary cracks") is formed (Fig. 2a). The extent of the secondary cracks depends on the additional stresses induced by the reinforcement, which at this stage has to hold together the concrete previously split by the principal cracks. The more closely the reinforcement follows the direction of the principal stress, the smaller is the importance and the extent of the secondary cracks; in theory, no secondary cracks occur if the reinforcement conforms exactly to the direction of the principal tensile stress.

Stirrups and Inclined Bars.

Fig. 1a shows that if a principal force is balanced by a force in an arbitrary direction at an angle smaller than 90 deg., measured from the normal to the plane on which the force is acting, an additional shearing force must be present if the system is to be in equilibrium. This well-known result is based on the assumption that the strains in the concrete and the steel are equal. After the concrete has cracked along the principal planes no shearing force can operate along the crack. An immediate redistribution of internal forces and stresses occurs, which causes an angular displacement of the principal planes and the formation of secondary cracks along the new lines of principal stress (Fig. 1b).

The extent of these secondary cracks increases as the load increases; it is possible for one or more to unite with a major primary crack, the resulting "rupture-line" leading possibly to a premature failure in bending. (From Fig. 2b it is obvious that if the resistance of stirrups to bending is neglected the longitudinal reinforcement at A must resist the bending moment which occurs at B.) Vertical stirrups cause the inclined cracks to extend longitudinally, and inclined bars which follow more nearly the curves of principal stress, should preferably be used. The effect of stirrups in resisting bending, the pitch of the stirrups, and the influence of cracks on the resistance-moment diagram are discussed later.

In Fig. 2c the equilibrium of part of a beam at a principal crack is shown, and the corresponding force diagram is shown in Fig. 2d. Assuming that the shearing force exceeds the shearing strength of the concrete, the basic equations of equilibrium lead to formulæ (1) to (3).

$$M = bd_n u_{cc}(d_1 - \frac{1}{2}d_n) + Q_s(x \sin \alpha - y \cos \alpha) \quad (1)$$

$$Q = bd_n u_{cs} + Q_s \sin \alpha \quad (2)$$

$$T = bd_n u_{cc} - Q_s \cos \alpha \quad (3)$$

It follows from Fig. 2c that the distance between the inclined bars is as important as the area of the bars. At least one bar (or in the case of stirrups, a pair of bars) should pass through each inclined crack, and this means that the spacing of the stirrups or inclined bars is limited by the horizontal projection h of the inclined cracks. From this requirement the intensity of the force Q_s induced in the shearing reinforcement can be computed. The inclinations and lengths of the inclined cracks can be obtained either accurately by computing principal stresses and planes, or approximately by comparison with the known principal stresses and planes of similar test beams with similar loading; the latter method is usually more convenient and sufficiently accurate. Since the positions of the cracks cannot be predicted accurately, limiting values can be obtained for Q_s and T , depending on the relative positions of the cracks and the reinforcement. The greatest value of Q_s and the least value of T , are obtained if the shearing reinforcement is located at the outer end of the crack (adjacent to the main reinforcement), since it must then resist both that part of the shearing force Q which cannot be resisted by the compressive zone, and the greatest proportion of the bending moment. Conversely, the least value of Q_s and the greatest value of T occur if the shearing reinforcement is located at the inner end of the crack. In the latter case, if stirrups are provided, no bending moment is resisted by the stirrups and the main tension reinforcement at A' must resist the bending moment at section BB' which is obviously greater than that at section AA' (Figs. 2b and 3). For these two limiting cases the following analysis applies.

GREATEST VALUE OF Q_s (LEAST VALUE OF T).—Formula (1) becomes

$$M = bd_n u_{cc}(d_1 - \frac{1}{2}d_n) + Q_s h \sin \alpha \quad (1a)$$

Q is as given by formula (2), from which $d_n = \frac{Q - Q_s \sin \alpha}{b u_{cs}}$; substituting in (1a) and simplifying,

$$Q_{s(max)} = \frac{2\gamma Q - \beta d_1 + h + \sqrt{(\beta d_1)^2 - 4\gamma(M - hQ) - 2\beta d_1 h + h^2}}{2\gamma \sin \alpha} \quad (4)$$

GREATEST VALUE OF T (LEAST VALUE OF Q_s).—From formula (1),

$$M = bd_n u_{cc}(d_1 - \frac{1}{2}d_n) - Q_s(d_1 - d_n) \cos \alpha \quad (1b)$$



Fig. 3.—Resistance to Bending after Cracking.




Fig. 4.—Distortion of Bar across a Crack.

Since Q is given by formula (2), d_n is as in the foregoing; hence from (1b)

$$M = \beta(Q - Q_s \sin \alpha) \left(d_1 - \left[\frac{Q - Q_s \sin \alpha}{2b u_{cs}} \right] \right) - Q_s \cos \alpha \left(d_1 - \left[\frac{Q - Q_s \sin \alpha}{b u_{cs}} \right] \right),$$

from which $Q_{s(\min)}$

$$= \frac{K(2\gamma Q - \beta d_1) + \sqrt{\left(\frac{4\gamma Q}{\beta} \left[\frac{\gamma}{\beta} d_1 \right] + d_1^2 \right) \cos^2 \alpha - (4\gamma M - [\beta d_1]^2) L \sin \alpha}}{2\gamma L \sin \alpha} \quad (4a)$$

where

$$K = \sin \alpha + \frac{\cos \alpha}{\beta} \quad \text{and} \quad L = \sin \alpha + \frac{2 \cos \alpha}{\beta}.$$

Also

$$T_{\max} = \beta(Q - Q_s \sin \alpha) - Q_s \cos \alpha \quad (3a)$$

which is $\beta(Q - Q_s)$ for vertical stirrups.

Theoretical considerations show that the final slope of an inclined bar, after its yield point is reached in a widening crack, is between δ and ω . In Fig. 4a is shown the calculated shape of the centre-line of the bar after yield, disregarding the high bearing stress induced in the concrete by the acute change of direction of the bar. In practice the deformation of the bar must approximate to that shown in Fig. 4b; thus the greater of the two angles δ and ω should be allowed for in computing T_{\max} , and a value intermediate between δ and ω would be reasonable for computing $Q_{s(\max)}$. Most investigators agree that a suitable value for β is between 5 and 6.

Since the compressive zone is always subjected to combined shearing and compression, the greatest compressive stress occurs on a plane inclined to the axis of the beam. Hence when the whole compressive zone is required to resist bending, a reduced value of u_{ce} should be used. Theoretical calculations indicate that $0.8u_{ce}$ is adequate.

Only the limiting spacing of the reinforcement is considered in the foregoing. For practical reasons, such as ease of placing and compacting the concrete, it is usually desirable to place the reinforcement at the greatest permissible spacing and the formulae given are convenient for this purpose. On the other hand, a spacing smaller than the maximum produces a better distribution of stress and should be adopted when practicable. This case is more indeterminate than the limiting conditions considered in the foregoing, but the problem can be solved



Fig. 5.—Equivalent Resistance of Reinforcement.

in the same way by considering the plastic properties of the reinforcement, using the resultant of the oblique forces produced by each separate bar. When the value of δ is obtained in this way Q_s can be calculated by considering the forces $Q_1, Q_2, Q_3 \dots Q_n$ to be proportional to the areas $A_1, A_2, A_3 \dots A_n$ (Fig. 5). This assumption can be made only if ductile steel is used, and even so restricted strains should be allowed.

Application to Design.

Contrary to the assumption in the elastic theory, a plane section does not remain plane after bending, but comprises a curve A'B' and a plane B'B joining at B' (Fig. 3). The amount of main tension reinforcement calculated for the relevant (and fictitious) elastic cross-sections should extend beyond the non-planar sections, as shown in the following.

Since $Q < b \cdot d_n u_{cc}$ and $M = b d_n u_{cc} (d_1 - \frac{1}{2} d_n)$, $\frac{M}{Q} > \beta d_1 - \frac{\beta^2 Q}{2 b u_{cc}}$ (Case A).

The resistance-moment diagram is plotted in the usual manner, and is then extended by distances h equal to the horizontal projections of the lengths of the cracks (Fig. 6).

If $\frac{M}{Q} < \beta d_1 - \frac{\beta^2 Q}{2 b u_{cc}}$ (Case B), with stirrups, formulæ (4a) and (3a) could be used to compute the value of T_{max} , but these give the same result as the simple formulæ derived for the case of pure bending.

Consider the case of simple bending in which the resistance of the compressive zone to shearing equals the shearing force Q . Then $\frac{b d_n u_{cc}}{\beta} = Q$; $d_n = \frac{\beta Q}{b u_{cc}}$.

In Case A, $M = \beta Q d_1 - \frac{\beta^2 Q^2}{2 b u_{cc}}$ (5)

Since $T = b d_n u_{cc}$, $T = \beta Q$.




Fig. 6.—Adjustment of Bending Moment.

Now consider the case of combined bending and shearing. Substituting the bending moment given by (5) in (4a), and simplifying,

$$Q_{s(min)} = \frac{2\gamma Q - \beta d_1 + \sqrt{\beta^2 d_1^2 - 4\beta d_1 \gamma Q + 4\gamma^2 Q^2}}{2\gamma} = 0$$

(that is, no shearing reinforcement is required) and $T = \beta(Q - Q_s) = \beta Q$, as before.

$$\text{If } M = 0, \text{ then } Q_{s(min)} = \frac{2\gamma Q - \beta d_1 + \sqrt{\beta^2 d_1^2}}{2\gamma} = Q.$$

Similarly in Case B, $T = \beta d_n u_{ec}$ which is equal to the value calculated by the formula for simple bending. Consequently the simple method of plotting the resistance-moment diagram shown previously can still be used and the shearing reinforcement can be obtained by deducting the shearing resistance Q_e of the compressive zone from the total shearing force and resisting the rest of the shearing force by stirrups. The value of Q_e is $\frac{T}{\beta}$ and the area of stirrups A_{sv} is

$$\text{given by } A_{sv} = \frac{Q - Q_e}{2f_u} \quad (6)$$

The design of a beam can therefore be reduced to the following simple procedure. Design the beam as if it is subjected to pure bending only. Then calculate the shearing resistance of the compressive zone of the section thus obtained, and deduct this from the shearing force. Provide stirrups to resist the balance.

Columns subjected to combined compression, bending, and shearing, or statically-indeterminate structures in which stresses due to shrinkage are considered, can be treated in a similar way. The structure is first designed to resist only the eccentric thrust or pull; the values of d_n and Q_e are then determined and stirrups are provided to resist the balance of the shearing force.

In the case of inclined bars, the same principles should be followed. It follows from Fig. 2c that if the line of action of Q_s is chosen so that it passes through the point O, this force has no influence on the position of the neutral axis [formula (1)]. Hence the cross-section can be designed for bending (or combined bending and compression or tension) and the effect of shearing can be considered separately by balancing $Q - Q_e$ with a force at an angle α to the axis

$$\text{of the beam. In algebraic terms, } Q_s = \frac{Q - Q_e}{\sin \alpha} \text{ and } A_{st} = \frac{Q - Q_e}{f_u \sin \alpha} \quad (7)$$

Thus Q_s becomes greater and T becomes smaller than in the equivalent case when stirrups are used. Since T can be reduced even to zero, this can be considered as a limiting case in which no cracks can open. It is generally accepted that the depth to the neutral axis does not exceed about $0.5d_1$, that is

$$\frac{f_u}{\beta d_1 u_{ec}} [A_{st} + A_{sv} \cos \alpha] < 0.5.$$

Since ultimate stresses are not generally used directly in design, allowable working stresses and load-factors should be inserted in the appropriate formulae to conform to relevant regulations. In particular, the simplifications made in deriving formulae (6) and (7) are valid only if the stress f_u is reduced by 20 to 25 per cent. to allow for the effect of the bending moment on the web reinforcement.




Fig. 7.

In formulæ (6) and (7), if Q represents the applied shearing force and Q_0 the safe resistance of the compressive zone, f_u should be replaced by the safe tensile stress p_{st} in the shear reinforcement. Likewise, u_{cc} should be replaced by the safe mean compressive stress p_{cm} in the concrete which is about $\frac{1}{3}u_{cc}$ where u_{cc} is two-thirds of the crushing strength.

EXAMPLE.—Design the shear reinforcement for the beam shown in Fig. 7 if p_{st} is 20,000 lb. per sq. in. and the crushing strength of the concrete is 3000 lb. per sq. in. at 28 days ($p_{cb} = 1000$ lb. per sq. in.). Assume $\beta = 6$. To resist the positive bending moment the reinforcement required is seven 1-in. bars, but eight are provided since two of the bent-up bars are not fully effective in resisting bending moment (see the bending moment diagram in Fig. 7).

At centre of supports: Applied shearing force $Q = (2750 \times 8) + 22,000 = 44,000$ lb.

Section 1—1.—

Applied $M_1 = (44,000 \times 4 \times 12) - (2750 \times 4^2 \times 12 \times \frac{1}{2}) = 1,848,000$ lb.-in.

Applied $Q_1 = 44,000 - (2750 \times 4) = 33,000$ lb.

$\frac{M_1}{bd_1^2 p_{cb}} = \frac{1,848,000}{15 \times 25.5^2 \times 1000} = 0.190$; hence from formulæ* based on those in

B.S. Code No. 114, $a_1 = 0.848$ and $n_1 = 0.344$. Since $p_{cm} = \frac{1}{3} \times \frac{2}{3} \times 3000 = 667$ lb. per sq. in.,

Safe $Q_{c1} = \frac{T}{\beta} = \frac{bd_1 p_{cm}}{\beta} = 15 \times 0.344 \times 25.5 \times 667 \times \frac{1}{6} = 14,600$ lb.

From formula (7) with bars bent up at 45 deg., and p_{st} substituted for f_u ,

$A_{st1} = \frac{33,000 - 14,600}{20,000 \times 0.707} = 1.30$ sq.-in., say two 1-in. bars.

Similarly for Section 2—2.—

$M_2 = (44,000 \times 2 \times 12) - (2750 \times 2^2 \times 12 \times \frac{1}{2}) = 990,000$ lb.-in.

$Q_2 = 44,000 - (2750 \times 2) = 38,500$ lb.

$\frac{M_2}{bd_1^2 p_{cb}} = \frac{990,000}{15 \times 25.5^2 \times 1000} = 0.102$; hence $a_1 = 0.917$ and $n_1 = 0.167$. As at

$$*a_1 = \frac{l_a}{d_1} = \frac{1}{2} \left(1 + \sqrt{1 - \frac{3M}{bd_1^2 p_{cb}}} \right) \quad \text{and} \quad n_1 = \frac{d_a}{d_1} = 1 - \sqrt{1 - \frac{3M}{bd_1^2 p_{cb}}}$$

Section 1—1, $Q_{c2} = 15 \times 0.167 \times 25.5 \times 667 \times \frac{1}{4} = 7100$ lb. and

$$A_{st2} = \frac{38,500 - 7100}{20,000 \times 0.707} = 2.22 \text{ sq. in., say three 1-in. bars.}$$

The bars are arranged as in Fig. 7. Anchor bars are provided at the ends of the bars owing to restricted bond length available.

An Architectural Award.



ONCE again a reinforced concrete building has been awarded the London Architecture Bronze Medal which is awarded annually by the Royal Institute of British Architects for a building of exceptional merit. The building is a block of flats in St. James's Place; the rear of the building, which is shown in the accompanying illustration, overlooks Green Park. The structure is basically a reinforced concrete frame but is faced with Baveno grey granite and blue brick. The main problem in the architectural design is harmonising a structure of modern appearance with adjacent eighteenth-century buildings.

The floors, which are of cast-in-situ construction, are $7\frac{1}{2}$ in. thick, thereby allowing the solid partitions to be re-positioned at any time. The columns are of H-section and provide ducts for services. The edge beams, which are wide and shallow, support the cantilevered balconies; the soffits of the beams are at ceiling level. Stability is provided mainly by the reinforced concrete lift-walls and stair-wells. The exposed concrete of the penthouse is white with a boarded finish, and the requirements of strength and colour are obtained by a 1 : 1 $\frac{1}{2}$: 3 mixture, the cement portion being a 1 : 3 mixture of white cement and ordinary Portland cement.

The architects are Messrs. Denys Lasdun & Partners and the consulting engineers are Messrs. Ove Arup and Partners. The contractors were Messrs. J. Jarvis & Sons Ltd.

Production of Aggregates.

The production of building and concreting sands and gravel aggregates in Great Britain in 1960 was, according to "Sand and Gravel Production 1959-1960" (Her Majesty's Stationery Office; price 1s. 3d.), 64,500,000 cu. yd., which is 11 per cent. higher than in 1959. In general, output has increased in all regions excepting Mid-Anglia where the output in 1959 was abnormal because of the

demand for aggregates used in the construction of the motorway M1. In view of the large increase in the use of aggregates required for the increasing amount of construction work, it is estimated that the demand for sand and gravel will continue to increase, although not necessarily as rapidly as in the past two years, and that the total demand in England and Wales may reach 73,000,000 cu. yd. by 1970.

A Practical Comprehensive Method of Designing Reinforced Concrete Sections.—IV.*

By J. RYGOL, B.Sc.(Eng.).

LOAD-FACTOR METHOD (continued).

American Practice.—In the American report quoted on page 275 of this journal for August 1961, the ratio α/n is given as 0.85 for concrete having a cylinder strength of 5000 lb. per square inch. According to recent tests,⁽³⁾ this ratio applies to concrete having a cylinder strength of 4000 lb. per square inch (that is a cube strength of 5333 lb. per square inch), and is reduced by 0.05 for each 1000 lb. per square inch of cylinder strength (or for each 1333 lb. per square inch of cube strength) in excess of 4000 lb. per square inch, as in the example which follows.

EXAMPLE NO. 15. Given.—Triangular section. $b = 14$ in. $d = 7$ in.
 $A_s = 1.80$ sq. in. $A_s' = 0$. $f_y = 45,000$ lb. per sq. in.
 $f_{cpd} = 6300$ lb. per sq. in.; therefore $f_u = 0.85 \times 6300 = 5350$ lb. per sq. in.
 To determine.—Ultimate bending resistance of the section.

$$\text{Solution.}—\bar{p} = \frac{1.80}{7 \times 14} = 0.01836; \bar{q}_{yb} = r = 0.01836 \times \frac{45,000}{5350} = 0.154.$$

From Nomogram No. 5 (with $\gamma = 0$, $r = 0.154$), $\alpha = 0.554$, but

$$e_s = \frac{45,000}{30 \times 10^6} = 0.0015; \eta = \frac{0.003}{0.0015 + 0.003} = 0.667.$$

$\alpha = \left[0.85 - \left(\frac{6300 - 4000}{1000} \times 0.05 \right) \right] \times 0.667 = 0.493$; hence the mode of failure of the section is controlled by crushing of the concrete. Thus

$$m_u \bar{p} = \frac{30 \times 10^6 \times 0.003}{5350} \times 0.01836 = 0.309$$

and the compatibility of strains leads to the equation

$$\alpha - \frac{\alpha(2 - \alpha)}{2} - \frac{(0.74 - \alpha)}{\alpha} \times 0.309 = 0, \text{ from which } \alpha = 0.517.$$

From Nomogram No. 6 (with $\gamma = 0$, $\alpha = 0.517$), $\bar{C}_{ut} = 0.0875$.

$$\bar{M}_{ut} = 0.0875 \times 5350 \times 14 \times 7^2 = 321,000 \text{ in.-lb.}$$

$$\text{Thus } \eta = \frac{\alpha}{0.74} = \frac{0.517}{0.74} = 0.698,$$

$$e_s = \frac{1 - \eta}{\eta} \times e_u = \frac{1 - 0.698}{0.698} \times 0.003 = 0.001297$$

and $f_s = E_s e_s = 30 \times 10^6 \times 0.001297 = 38,900$ lb. per sq. in., which is less than the yield point stress $f_y = 45,000$ lb. per sq. in.

Mode of Failure.—Figs. 9 and 10 (pages 271 and 273 of the number for August 1961) should be transposed. The diagram on page 271 depicts conditions when failure is controlled by crushing of the concrete, and that on page 273 applies when controlled by yielding of the steel.

REFERENCE.

3.—“Ultimate Strength of Non-rectangular Structural Members.” By A. H. Mattock and L. B. Kriz. Journal of the American Concrete Institute, January, 1961.

* Concluded from August, 1961.

Book Reviews.

"Failure and Repair of Concrete Structures." By S. Champion. (London: Contractor's Record Ltd. 1961. Price 35s.)

It can be said with truth that the author of this book has succeeded in his purpose of compiling a useful report dealing with the engineering rather than the scientific aspect of the deterioration and maintenance of concrete structures. The importance of the correct diagnosis of the cause of a failure is stressed. Many cases of defects due to chemical attack are considered and the part played by the cement in such cases is emphasised. The short early part of the book, which deals with such cases together with mechanical causes of failure (that is oversteering, shrinkage, thermal and moisture changes, and the like), is followed by the major part which deals in a practical manner with methods of repair. The scope of this part is extensive since it ranges from dealing with cracks (a particularly good section) to underpinning. The special case of failure of prestressed concrete structures is considered briefly but realistically and fifteen potential causes of failure are itemised.

"The Elementary Principles of Reinforced Concrete Design." By W. H. Elgar. (London: The Architectural Press. 1961. Price 18s. 6d.)

As the title implies, this book gives the bare outlines of the basis of design of simple reinforced concrete building components, and as such is a suitable introduction to the subject for students of architecture and building for whom it is intended. Even so, the load-factor method, flat slabs, shells and prestressed concrete are included but are necessarily dealt with in a superficial manner. Although there are only about a hundred pages of text in large type with numerous exceedingly clear diagrams, the contents include most of the salient matters expected to be covered in an elementary book. Many examples are given, although some of the few details of reinforcement may be open to criticism. The introduction contains a number of weak statements, which may be misunderstood by a thoughtful reader, but elsewhere the phraseology is good and concise.

"Innovations in Building Materials." By Marian Bowley. (London: Chatto & Windus Ltd. 1960. Price 70s.)

This book is one of a series on industrial innovations. The author is a reader in political economy and the work comprises a considerable collation of documents, data, and descriptions of various aspects of the building industry, but in particular the materials brick, concrete and glass, with some reference to aluminium and asbestos-cement. The term innovations is used fairly loosely since the classification relates to developments since the early nineteenth century, and to innovations before and since the first world war.

The subject-matter is drawn from numerous sources, but nevertheless the scope of publications searched for information seems to be limited especially where concrete is concerned. The references for this material are largely to architectural journals. There are, however, some interesting commentaries on the cement and precast concrete industries.

Since the writing, although factual, is somewhat discursive, it would be an advantage if the conclusions given at the end of each chapter were more concisely written instead of being equally wordy and containing many diversions.

"Architects' Detail Sheets." Edited by E. D. Mills. (London: Liffé Technical Publications Ltd. 1961. Price 35s.)

It is generally believed that most reinforced concrete detailers lack knowledge of practical building construction. (It is likewise alleged that many architectural draughtsmen are deficient in practical knowledge of structural engineering details.) If the former statement be true, these sheets of sketches, which are the fifth in a series of similar publications, will help greatly to meet the deficiency. As in the previous publications, ninety-six large and clear drawings are given of various building details, including the attachment of various building components to concrete floors, roofs, balconies, walls and stairs. These are not merely text-book details, since most are taken from actual named structures. Although many of the details relate to concrete, others are concerned with construction in brickwork, timber and steel.

The £.s.d of OSAL*

—Waterproofing Cement
Renderings

It's not the cost
per gallon
but
the cost per yard
that counts

On this basis Tricosal, which waterproofs a square yard of 3/1 sand and cement renderings $\frac{3}{4}$ in. thick for only 34d., is the most economical as well as the most efficient additive. It waterproofs integrally and, being a liquid, mixes with the gauging fluid and is evenly distributed throughout the mix.

*Now supplied in
non-returnable
containers*




For 30 years or more Tricosal has been specified by leading Architects not only for waterproofing but for hardening cement and concrete and increasing their resistance to oils and acids. Send for Information Leaflet No. 1.

* Osal is the generic name for the products of A. A. BYRD & CO. LTD.—Florosal, Neocosal, Tricosal and Lubrosal. Literature about each individual product is available on request.

A. A. BYRD & CO. LTD. (Dept C9) 219 TERMINAL HOUSE, GROSVENOR GARDENS, LONDON, S.W.1
Phone: SLOne 5236 Grams: Byrdcom, Wasphone, London Works: Basingstoke, Hants

Pattern of service in the concrete age



**SPECIALIST
ENGINEERS & CONTRACTORS**

THE MODULAR CONCRETE CO. LTD.
(Construction Division)

1260 London Road, Norbury, S.W.16
Telephone: POLLards 5000

Modular Construction Division specialises in foundations and reinforced concrete frames for all types of buildings.

Illustrated is a ten-storey maisonette block and library recently constructed by Modular for the London County Council at Danebury Avenue, Roehampton.

*L.C.C. Principal Architect: Hubert Bennett, F.R.I.B.A.
Consulting Engineer: W. V. Zinn, B.Sc., M.I.C.E.,
M.I.Struct.E., M.Com.E.*

Concrete Avalanche Sheds.



Fig. 1.

THE accompanying illustrations (Figs. 1 and 2) show a concrete tunnel 1036 ft. long in the course of construction on the Trans-Canada Highway. The tunnel, which is of precast and cast-in-situ reinforced concrete, is one of a number required to protect the road from avalanches so as to maintain an all-weather route through the Rocky Mountains. It is situated 25 miles to the east of Revelstoke, British Columbia. It was constructed in 3½ months in time for the winter of 1960. Instructions were given to the workmen that the site was to be vacated immediately in the event of warning of a 65-per cent. probability of an avalanche occurring. The necessity for completion by the middle of November is emphasised

by a warning of a 55-per cent. probability which occurred on November 3, 1960.

All plant, equipment and stores had to be transported 450 miles by rail from Vancouver and, because of the urgency of the work, over two thousand concrete units were precast in Vancouver. For the cast-in-situ work nearly 1000 tons of reinforcing steel was delivered to the site. A labour camp to accommodate up to 150 men was erected near the site.

The tunnel is designed to withstand a vertical load of 1100 lb. per square foot. The structure has a clear internal span of 36 ft. and an internal height of 14 ft. 6 in. at the front and 21 ft. at the rear. Precast concrete columns 12 in. by 30 in. in cross-section are provided at 7-ft. centres




Fig. 2.

at the front, and cast-in-situ columns 48 in. square are provided at the rear at 14-ft. centres. The rear columns are connected by tie-beams 40 ft. long to a continuous anchor-wall 2 ft. wide and 8 ft. deep. The roof comprises prestressed precast beams, each about 40 ft. long, 42 in. wide and 36 in. deep, laid alongside each other.

The consulting engineers acting for the Government of British Columbia are Messrs. Choukalos, Woodburn, Hooley and McKenzie. The contractors were Messrs. John Laing and Son (Canada), Ltd., which firm has recently been awarded contracts for the construction of two

further avalanche tunnels over the Trans-Canada Highway near Lanark, also in British Columbia. The new work commenced recently and must be completed by early November this year to avoid danger from avalanches. The construction is to be similar to the earlier work and comprises cast-in-situ and precast reinforced concrete. More than 1700 precast units are to be used, including about three hundred 17-ton prestressed precast roof beams. Over 15,000 cu. yd. of excavation, much of it in rock, will be necessary and about 600 tons of reinforcing steel are to be used.

Bags for Batching Concrete Materials.

A NEW type of container for transporting or storing the materials, including the water, for a batch of concrete in an un-mixed condition and in the proportions required, has been developed recently in the U.S.A. by Rodeffer Industries, Inc., of California. The container is a collapsible rubber bag 6 ft. high and divided

into two compartments having a combined capacity of $1\frac{1}{2}$ cu. yd. The smaller central cylindrical compartment contains the cement, and is sealed off from the outer annular compartment which contains the coarse and fine aggregates and the water. While being filled the empty bag is hoisted on to a movable platform below the outlets of a batching plant from which all the ingredients for the concrete are discharged into the bag. The bag is then transferred to a 5-ton fork-lift truck which conveys it to a store, or, by other means, the filled bag is transported to the site. When concrete is required, the bag is hoisted bottom upwards (Fig. 1), a pin is withdrawn and the contents are discharged directly into the mixer.

It is claimed that closer control of the concrete mixture is obtained and that few alterations are required to be made to a batching plant at which the bags are filled. It is also claimed that a bag can be used up to a thousand times before replacement is necessary, and when empty it can be dropped safely to the ground if mixing concrete at a height. It is estimated that in the U.S.A. the use of large numbers of these bags may reduce the cost of batching concrete by as much as 75 per cent. Fluctuation of demand for concrete at the site can be dealt with as filled bags can be held in stock until required, thereby enabling batching plants to be in continuous use irrespective of the immediate requirements.




Fig. 1.

for the design and supply of **PRESTRESSING BEDS** and **EQUIPMENT**

you-too-can rely on

One of a batch of
Stelmo prestressing beds
supplied to Richard Costain Ltd.



who offer a unique service in providing
the most economical layout for your
works or on the site for the production
of pre-cast concrete. It
includes the design and supply
of prestressing beds, jigs, and
wire-handling equipment,
jacks, anchors, etc.,
all specially designed to
suit your conditions.



*the most comprehensive
mould service in the world*

STELMO LTD • WESTWELL LEACON • CHARING • ASHFORD • KENT. Tel: Charing 395-7

When you said: I wouldn't touch additives!
You couldn't have known about
POZZOLITH



Pozzolith—with unique facilities like this mobile laboratory—is more than an additive. It is a means to quality control.

Additives have contributed to the building of many magnificent concrete structures, but only too often they are not intelligently applied and do not give the intended results.

So that you might see the role of additives in true perspective, Pozzolith—the world's leading water reducing admixture, invented as far back as 1932—has recently been introduced to this country. You

now have the opportunity to see and appreciate the values of this concrete control; demonstrated and explained by men who know what concrete will and will not do. Behind them is a research unit unmatched in this field. And on every project on which the Pozzolith method is used, engineers will be on hand to provide unique, on-the-spot, technical assistance.

Write for further details to

Manufactured and distributed in Great Britain by
MILLARS' MACHINERY COMPANY LIMITED,
Pinners Hall, Great Winchester Street,
London, E.C.2.
Tel: London Wall 4266

POZZOLITH

Millars

Under license from THE
MASTER BUILDERS CO.
A Division of American
Marietta Company.

Standard Prestressed Beams.

IN the number of this journal for May 1961, dimensions are given of standard prestressed concrete beams in accordance with a report recently issued by the Prestressed Concrete Development Group. The first bridge incorporating such beams has been built by the Central Electricity Generating Board and provides access over a main drainage channel to a sub-station at Whitson, near Newport, Monmouthshire. The bridge has a clear span of 46 ft. and allows for future widening of the channel. The design load was based on the heaviest load which it is anticipated will cross the bridge, namely a 165-ton transformer; beams of one of the standard sections and 48 ft. long, with a cast-in-situ reinforced concrete deck, are capable of carrying this load. The rein-

forced concrete abutments are supported on piles 40 ft. long. The bearings for the beams (Fig. 2) are bull-head rails laid on each abutment, on which bears a flat steel plate embedded in the underside of each beam.

Since it was impracticable to launch the beams into position from the side, as a public road would thereby be obstructed, a temporary bridge was built on to which the low-loader delivering the beams was driven. The beams were lifted off the low-loader and placed in position by two cranes, one at each abutment, working together (Fig. 1). The unloading and placing of each beam took about five minutes; all the beams were placed in two days.

The bridge was designed by the Trans-




Fig. 1.




Fig. 2.

mission Project Group of the Central Electricity Generating Board. The contractors were Messrs. A. Jackaman & Son, Ltd. The precast beams were made by Anglian Building Products, Ltd.

Change of Address.

THE Indented Bar and Concrete Engineering Co., Ltd., have now removed to 67-69 Salcott Road, London, S.W.11 (Telephone—BATtersea 4121).

British Standard Notation for Concrete Structures.

PART 4 of British Standard No. 1991, "Recommendations for Letter Symbols, Signs and Abbreviations", was published recently and deals with the notation for "Structures, Materials and Soil Mechanics". In general the symbols for reinforced concrete conform to those in B.S. Code of Practice No. 114, but many more items are given.

The terms in the following are exactly as given in the Standard, which also includes basic symbols, and symbols for use in steel structures, aircraft structures, soil mechanics and stress analysis. Standard abbreviations for units of measurement and the like are also given. The complete list for concrete structures is as follows.

DIMENSIONS

Length or span	l, L
Height	h
Depth	d, D
Effective depth from compressive face to tensile reinforcement	d_1
Depth from compressive face to neutral axis	$n_1 d_1, d_n$
Depth from compressive face to compressive reinforcement	d_2
Breadth	b
Thickness	t
Radius	R
Diameter	D
Lever arm	$a_1 d_1, l_n, a$
Eccentricity	e
Pitch	s
Sum of perimeters of tensile reinforcement	o
Area of column or beam	A
Area of concrete	A_c
Area of steel	A_s
in tension	A_{st}
in compression	A_{sc}
Area of web or shear reinforcement	A_w
Equivalent area of helical or binding reinforcement (volume of helix/length of column)	A_h
Area of concrete in column core	A_k

PROPERTIES OF SECTIONS AND MATERIAL CONSTANTS.


Moment of inertia; second moment of area	I
Radius of gyration	k
Modulus of section	Z
Moment of resistance in bending	M_r
Flexural stiffness of a member (I/I)	K
of a beam	K_b
of an upper column	K_u
of a lower column	K_l
Percentage of reinforcement	ρ
Equivalent area of section in terms of concrete	A_e
Modulus of elasticity (direct) or Young's modulus	E
of concrete	E_c
of steel	E_s
Modular ratio (E_s/E_c)	m
Modulus of rigidity, or shear modulus	G
Bulk modulus (modulus of compressibility)	K
Poisson's ratio	ν, \dots, σ

EXTERNAL LOADS AND PRESSURES.

Load or weight, concentrated or total	W
Load or weight, distributed (divided by length or area)	w
Vertical reaction	V
Horizontal reaction	H
Resultant reaction	R

FORCES AND MOMENTS.

Direct force	F
in concrete	F_c
in compression	F_{cs}
in tension	F_{ct}
in steel	F_s
in compression	F_{sc}
in tension	F_{st}
Permissible force	P
in concrete	P_c
in steel	P_s
Shear force	Q
Bending moment	M
Fixed end moment	M_f



**THE CHANGING SCENE
IN BRITAIN
OWES MUCH TO
TUNNEL CEMENT**

Tunnel Cement is playing a big part in today's building programmes, with a range that includes Masonry, White and Coloured Sulphate Resisting, Rapid Hardening and Waterproof Cements.

The Tunnel Portland Cement Company Limited,
185, Piccadilly, London, W.1.
Grosvenor 4199.

TUNNEL CEMENT



FOR RELIABLE BAG AND BULK DELIVERIES

CVS-50



20-STOREY FLATS AVONDALE SQ S.E.1

Clients: The Corporation of London

Architects: Sir Lancelot Keay, Basil G. Duckett & Partners

Consulting Engineers: Ove Arup & Partners

Main Contractors: Pauling & Co. Ltd.

PAULING

RUSH & TOMPKINS - PAULING GROUP

GREAT BRITAIN, SOUTH AFRICAN REPUBLIC, CANADA, BRITISH GUIANA, ADEN

STRESSES.

Direct stress	f
in concrete	f_c
in compression	f_{cc}
in tension	f_{ct}
in steel	f_s
in compression	f_{sc}
in tension	f_{st}
Permissible stress	p
in concrete	p_c
in compression	p_{cc}
in compression in bend- ing	p_{ccb}
in steel	p_s
in compression	p_{sc}
in tension	p_{st}
Concrete strength	
Cube strength	u
Equivalent cube strength	u_e
Cylinder strength	u_{cyt}
Preliminary cube strength	u_p
Works cube strength	u_w
Ultimate compressive strength in bending	u_b
Modulus of rupture	R
Steel strength	
Ultimate stress	f_u
Proof stress	f_p
Yield stress	f_y
Shear stress	q

STRAINS AND DISPLACEMENTS.

Direct strain	ϵ
in concrete	ϵ_c
in steel	ϵ_s
(with further modifications of subscripts as for direct stress if required)	
Shear strain	ϕ
Deflexion	δ, Δ
Angle of rotation	θ

**A Large Prestressed Concrete
Transmission-line Tower.**

IN this journal for June last, a brief description is given of a prestressed concrete transmission-line tower almost 100 ft. high, in Massachusetts. It has been pointed out by Messrs. Schupack and Zollman, the consulting engineers responsible for the design of the structure, that the wire guys described as stabilising the tower were attached only during erection but they were never used effectively. The tower is entirely a free-standing structure cantilevering vertically from the pile-caps.

September, 1961.

Bulletins Received.

"Annual Report of the City of Manchester Surveyor and Engineer's Department for 1960."—Contains illustrations and descriptions of civil engineering works carried out in 1960.

"Better Opportunities in Technical Education." Ministry of Education. (London: H.M.S.O. 1961. Price 1s. 3d.)—Gives the Government's proposals for reorganising the existing system of the technical college courses for technicians, craftsmen, and operatives.

"Rectangular Flat Slabs Supported on Columns." By H. Nylander. Bulletin No. 34. The Royal Institute of Technology, Stockholm. (In Swedish with a summary in English. 1959. No price stated.)

"Splicing of Cold-stretched Reinforcing Bars with Anchoring Rings." By C. Forsell. The Royal Institute of Technology, Stockholm. (In Swedish with a summary in English. 1960. No price stated.)

"Punching of Concrete Slabs Without Shear Reinforcement." By S. Kinnunen and H. Nylander. Publication No. 158. The Royal Institute of Technology, Stockholm. (1960. In English, Price Kr. 11.)

"The Temperatures Under Houses Erected Immediately on the Ground and the Heat Losses from their Foundation Slab." By O. Vuorelainen. Publication No. 53. The State Institute for Technical Research, Finland. (1960. In English. No price stated.)

"Suggestions for Requirements of Sound Insulation." The State Institute for Technical Research, Finland. (1960. In Finnish with a summary in English. No price stated.)

Detailing Reinforced Concrete.

THE City and Guilds Institute of London announce that they are to hold a course on the detailing of reinforced concrete structures. This course should enable those engaged in such work to attain a higher standard than is generally prevalent. This journal joins with the Joint Committee on Structural Concrete in hoping that design engineers will encourage their assistants to attend the courses which will eventually be held at various technical colleges throughout the country.

Computer Programmes for Structural Problems.

THE computer programmes prepared by the Cement and Concrete Association are given in the following list. Most of the programmes relate to structural analysis and are applicable to any material. Those that are suitable for prestressed concrete are marked with an asterisk. The Association should be consulted regarding the availability of these programmes and the type of computer for which each has been devised.

Solution of simultaneous linear equations.

A single-plane structural frame.*

Stressing of multiple-anchor 3-dimensional pipework systems.

Linear pin-jointed frames.*

Fundamental properties of beams of varying section.*

Composite action between beams and slab under transverse load.*

Elastic analysis of rigid-jointed plane structures.*

Stressing and deflections in piping systems.

Surveying by quadrilaterals.

Calculations of sag and tension of suspended cables.

Single-grid frames.*

Solution of a large number of simultaneous linear algebraical equations.

Solution of second-order partial differential equations with particular reference to torsion problems.

Simultaneous linear ordinary differential equations.

Cut and fill. (Two programmes.)

Plane frames, grillages, and space frames.*

Elastic skew slabs.*

Prestressed concrete sections*

Composite action between beams and slabs.*—I. Slab with identical span-wise beams repeated at equal intervals supported over several transverse supports; and with beams whose flexural stiffness varies across the span. (Two programmes.) II. Rectangular slab resting on four edge-beams and supported at the corners on rigid stanchions. (Two programmes.) III. Rectangular stiffened slab on elastic foundation.

Moment distribution.*

Laterally loaded piles.*

Slip circle analysis of the stability of earth dams.

Continuous beams.*—I. Slope deflection calculations. II. Fixed-end moments. III. Quarter-point deflections.

FIFTY YEARS AGO.

From "CONCRETE AND CONSTRUCTIONAL ENGINEERING", September, 1911.

Agricultural Products.



THE accompanying illustration, which shows one of the stands at the Royal Agricultural Society's Show held in Norwich in the summer of 1911, is of interest in view of the fact that concrete products and buildings are to be a feature (as they were last year) at the Royal Dairy Show to be held at Olympia, London, next month. The products exhibition in 1911 included cattle and pig troughs, flooring and roofing tiles, fence posts, cattle pens, rick posts, and blocks for walls.



Compare
this penetrating
ability * with anything you have ever used before

*** ROTOPUNCH PENETRATION**

Material	depth	time
Granite	2"	3 mins.
Concrete	1 1/2"	30 secs.
Hard Brick	2 1/2"	30 secs.
Stone (Portland)	2 1/2"	30 secs.
Soft Brick	1 1/2"	15 secs.
Breeze-block	2 1/2"	15 secs.

Using a 1" drill

- Produces quick, clean holes in all types of constructional materials.
- Ideal for fixing wall attachments, making entrances for pipes and fittings, grouting down machinery.
- Two tools in one—easy, fast change from percussion to normal drilling.
- Operator comfort is assured by the well balanced design and light weight.
- Low-cost—high productivity.

The unique

Wolf

ROTOPUNCH

ROTARY PERCUSSION DRILL

The Drill with the power to pierce granite



The versatile "Rotopunch" can help you and your business. So fill in the coupon NOW for an illustrated leaflet giving facts and benefits in detail — and POST TODAY.

TO: WOLF ELECTRIC TOOLS LTD., Dept. C.C.E.9, Pioneer Works, Manger Lane, London, W.3. Please send me the illustrated leaflet on the "ROTOPUNCH"

COMPANY _____

ADDRESS _____

MARK FOR THE ATTENTION OF _____

Branches at: BIRMINGHAM • BRISTOL • GLASGOW • LEEDS • MANCHESTER • NEWCASTLE • Agents throughout the World



ALAG

New!

A special aggregate for special purposes *

ALAG is a synthetic aggregate which, when used with CIMENT FONDU, PRODUCES CONCRETE WITH THE FOLLOWING UNIQUE PROPERTIES:—

EXTREME RESISTANCE TO ABRASION
(Hardness of aggregate 7.5 MOHS. Cuts glass)

ENORMOUSLY HIGH STRENGTH IN A MATTER OF HOURS

(For example 12,000 lb. per sq. inch at 24 hours and 16,000 lb. per sq. inch at 7 days)

HIGH DENSITY
(167 lb. per cu. ft. air-dried—20 lb. per cu. ft. higher than normal)

HEAT-RESISTANT
(up to 1150/1200° C.)

OR ALL ABOVE PROPERTIES COMBINED

SHOULD BE USED ONLY WITH HIGH ALUMINA CEMENT (CIMENT FONDU)

Write for further information. ALAG is available only from:—

LAFARGE ALUMINOUS CEMENT COMPANY LIMITED

73 BROOK STREET, LONDON, W.1. TELEPHONE: MAYFAIR 8546

The Late Mr. G. A. Maunsell.

MR. GUY ANSON MAUNSELL, whose death at the age of 76 occurred in June last, was well known for his interest in concrete and will be remembered for his designs, many of which were in advance of the practice of their day. His early civil engineering training was in connection with hydro-electric works in Switzerland and the naval base at Rosyth. He served in France in the Royal Engineers in World War I, and early in 1918 he was working on the design and construction of concrete ships and "mystery" towers. In World War II, he was responsible for the design of floating thin-slab concrete structures (see this journal for April, 1946).

Between the wars, he was first at the Ministry of Transport, then on the Falls of Clyde hydro-electric works with Sir William Arrol & Co., Ltd., and later on the widening of Putney Bridge with Messrs. Dorman Long & Co., Ltd. He then became managing-director of the Anglo-Danish Construction Co., which was formed for the construction of the famed Störstrom Bridge. In 1936 he opened a consulting engineering practice, in Westminster, from which he retired in 1959, and in which he was responsible for many well-known major structures.

Mr. Maunsell was a forthright all-round civil engineer; there are those who may remember that, in the mid-twenties, he might proceed with the construction of, say, a foundation in accordance with a sound practical design of his own devising without awaiting the delayed arrival of more intricate details from the drawing office.

Technical Writing.

A COURSE of six lectures, commencing on October 20, 1961, on "The Technique of Technical Writing" are to be given by various lecturers at Borough Polytechnic, London. The subjects dealt with will include style, common errors in style, sources of information, technical illustration, printing, and publishing. The lectures, particulars of which can be obtained from the Secretary, Borough Polytechnic, Borough Road, London, S.E.1, are intended for graduates (or equivalent status) with some experience in technical writing.

The Largest Dry Dock in the World.

CONCRETING in connection with the dry-dock at the Puget Sound Naval Shipyard, Washington, U.S.A., is now proceeding. The dock, which will be the largest dry dock in the world, is 1152 ft. long and 180 ft. wide, and there will be 42 ft. of water at mean low water.


The first stage of dredging unsuitable material, backfilling with selected material, cofferdam construction and dewatering has been completed. This work necessitated the removal of 600,000 cu. yd. of material. Below mean low-water level the material was removed by a suction dredge and by three derricks, with 3-cu. yd. buckets, mounted on barges. Selected filling was brought to the site and pumps mounted on barges sluiced the material into the water. Backfilling was built up along both sides of the dock to a level about 40 ft. below mean low-water level; the central portion was left at about the level of the base of the dock. A row of steel sheet-piles was driven along each side of the dry dock to form part of a cofferdam and will remain in place as part of the permanent construction. The outer end of the cofferdam consists of eleven circular sheet-pile cells of 60 ft. diameter. About 600,000 cu. yd. of backfilling was placed to complete the walls of the cofferdam. Before the cofferdam was closed sixty-six deep wells were sunk around the perimeter of the site, about 35 ft. inside the sheet-pile walls, for dewatering purposes. Three-hundred-and-ninety well-points were then installed at 10-ft. centres within the wells.

The second stage is the casting of the concrete floor and walls of the dock. Most of the floor will be a 7-ft. slab of reinforced concrete which increases to a thickness of 12 ft. under the main walls. The slab is being cast in sections 24 ft. by 40 ft. within steel shutters. The side walls, which are of reinforced concrete 12 ft. thick at the bottom and tapering to 2 ft. 9 in. at the top, are being cast in two stages, also using steel shutters. The walls have buttresses of precast concrete supporting galleries, tunnels and platforms at the top.

Patent Applications for Shuttering.

SHUTTERING is supported from tubular scaffolding (Fig. 1) by a turnbuckle comprising two rods 10, 11 with threads of opposite hand adjustably connected to a correspondingly threaded connecting loop 12 and each having a rotatable cross tube 15, 20 at its outer end. The tube 15 is held against axial movement within a collar 13 by welded abutments 16. The tube 20 is similarly held within two sleeves 19. In use, the tube 15 is laid on two horizontal scaffold tubes 21 and the shut-

ting in the shuttering for casting concrete (Fig. 4) of the parent Specification comprising panels having flanges 12 connected by bolts in slots 13 parallel with the face 10 of the panel, the edges of slots being inclined so that by forcing each bolt to a narrow end of a slot where the bolt engages both edges the edges and thus the faces 10 of the shutters are aligned, the facing member 10 is non-metallic, e.g. plywood. The flanges may be of angle section bar 14 to which is welded



tering supported from a tube 22 clamped at 23 to the cross tube 20. The turnbuckle may also be used horizontally. Specification 852,830 is referred to.—No. 852,918. May 16, 1958.

The soldier for concrete shuttering (Fig. 2) of the parent Specification has a concrete engaging face comprising a sheet 13 of resin bonded plywood screwed at 14 to angle bars 18 and surrounded by side sheets 17 of metal and a metal end plate 23. Zig-zag bars 19 are welded to the bars 18 and a bracing tube 11. In use, tie rods are passed through holes 22 and 21 to be tightened against short lengths of channel 20. The soldier is attached to adjacent shuttering by holes 16.—No. 853,591. October 28, 1958.

a strip 15 extending laterally beyond the bar 14 so as to protect the edge of the facing member 10, which is attached by bolts 16 to the bar 14 and cross-members 17 welded to the flanges 12. The panel 18 shown in Fig. 4 is adapted to be swung about bolts in the bottom slots 13 so that concrete can be poured into the shuttering. Stops 27 limit the opening of this panel.—No. 853,278. December 16, 1958.

[The foregoing Applications are in the name of Kwikform Ltd.]

Data for Pricing Reinforced Concrete.

Current prices are as given on page 296 of this journal for August, 1961.



September, 1961.

The system consists of 7 stress-relieved $\frac{1}{2}$ " diameter strands. The tendon is accommodated in a 2" diameter duct. Initial prestressing force is 181,000 lb. No cables have to be made up. Lightweight power-operated jacks are available. Grout holes and fixing holes are provided in the plate.

THIS SYSTEM COMBINES THE ADVANTAGES OF STRAND WITH ALL THOSE OF SINGLE WIRE STRESSING.

CCL

Seven Strand System



On a recent contract the Seven Strand System proved during operation to be the most economic per ton of force.

For details of the Seven Strand System and other CCL post-tensioning systems write to:

CABLE COVERS LIMITED

Prestressed Concrete Division
Technical Information Department

St. Stephen's House · Westminster · SW1

Telephone: ELM 7241

**Provides larger
prestressing
forces & lower
costs**



* FOR THE ADVANCEMENT
OF PRESTRESSING TECHNIQUES

MISCELLANEOUS ADVERTISEMENTS.

Situations Wanted, 5d. a word: minimum, 12s. Situations Vacant, 6d. a word: minimum, 15s. Other miscellaneous advertisements, 6d. a word: minimum, 15s. Displayed advertisements, 40s. per column inch. Box number 15. extra.

Advertisements must reach this office, 14 Dartmouth Street, London, S.W.1, by the 26th of the month preceding publication.

SITUATIONS VACANT.

SITUATIONS VACANT. Two assistant engineers required for progressive and busy private practice, Bedford Square, London, W.C.1 area. Must have specialised in reinforced concrete, good standard essential. Write for full details, stating age, qualifications and salary required, to Box 4772, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Garmon India, Private, Ltd., P.O. Box 503, Bombay, India, a leading firm of reinforced concrete bridge and general engineering contractors, invite applications from graduate Indian engineers returning home from abroad shortly, for their Design Office in Bombay.

SITUATIONS VACANT. Experienced part-time assistants required by consulting engineers, Westminster, for design and/or detailing of reinforced concrete bridges and buildings. Write in confidence, stating age and full details of experience and qualifications, to Box 4771, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Consulting engineers have vacancies for the following: Reinforced concrete designers with A.M.I.Struct.E.; Designer-detailers with H.N.C. or similar; Detailers with minimum two years' experience. The positions are permanent, with opportunity for advancement. Modern office and pleasant conditions. Salaries in accordance with experience. Apply BYLANDER, WADDELL & PARTNERS, 169 Wembley Park Drive, Wembley, or 10 Carver Street, Sheffield.

**ENGINEERING
DESIGNER/DRAUGHTSMEN**

required by
AIR MINISTRY
in London

Salary (inner London scale) Grade II, £1,048 to £1,215. Grade III, £658 to £1,048 (£866 at age 25). Starting salary depends on age, qualifications and experience.

Structural engineering designer-draughtsmen for reinforced concrete work of all types (Grades II and III).

Candidates should have served recognised apprenticeship or had equivalent training and also practical experience. Possession of recognised technical qualification an advantage—financial assistance and time off may be allowed for recognised courses of study for technical qualifications. Five days' week with 15 days paid leave per annum initially. Promotion and pension prospects. Some overseas tours with special allowances in addition to salary.

Applicants, who must be natural born British subjects, should write to AIR MINISTRY, W.G.d.(RL), LACOW HOUSE, THEOBALDS ROAD, LONDON, W.C.1, giving age, details of training, qualifications, full particulars of former posts held, or apply to any Employment Exchange quoting Kings Cross O/N.806. Candidates selected will normally be interviewed in London and certain expenses reimbursed. Only candidates selected for interview will be notified.

SITUATION VACANT. DAILEY, SON & CLARKE, Consulting Engineers, have vacancy for experienced reinforced concrete designer-detailer in their Clapham office. Age about 25 years, O.N.C. minimum qualification, enthusiastic and responsible, intending to progress. Wide variety of civil and structural projects. Good conditions for right man. 175 Lavender Hill, London, S.W.11. Telephone: BATHURST 4300.


SITUATION VACANT. Engineering assistant required to work in structural engineering department. Applicants should have minimum of three years' experience in reinforced concrete or steelwork. Permanent position. Five-days' week. Luncheon vouchers. Apply GENERAL MANAGER, ATCOST (FACTORIES) LTD., York House, High Street, Tunbridge Wells.

SITUATIONS VACANT. Reinforced concrete draughtsmen for permanent appointments. Good pay and prospects. Work varied and interesting in congenial group. Luncheon vouchers. M. M. KHAN, B.Sc., M.I.C.E., Consulting Engineer, 88 Rochester Row, London, S.W.1. Telephone: VICTORIA 9568.

SITUATIONS VACANT. Draughtsmen required, both junior and senior, to do work on precast or insitu, prestressed or reinforced concrete work. Salaries up to £1,100 per annum will be paid. Apply to the CHIEF ENGINEER, THE LONDON FERRO-CONCRETE CO. LTD., Maxted Close, Hemel Hempstead, Herts.

SITUATION VACANT. Detailer-draughtsman required for detailing of precast concrete frameworks. Write, stating age and experience, to A. & C. BAWIS LTD., Manor Works, Church Road, Thundersley, Essex.

SITUATIONS VACANT. Reinforced concrete and structural steelwork designers and detailers required at Bristol head office and in the London office. Permanent positions covering most fields of reinforced concrete and steelwork design. Pension and insurance schemes. Attractive salaries. Full details to NORRIS CONSULTANTS LTD., Beacon House, Queen's Road, Clifton, Bristol, 8.

Join the 

team of

**EXPERIENCED
REINFORCED
CONCRETE
DESIGNER/DETAILERS
and DRAUGHTSMEN**

at any of the Design Offices at

STAFFORD	LEEDS
LONDON	LIVERPOOL
BIRMINGHAM	MANCHESTER
BRISTOL	NEWCASTLE
CHELMSFORD	GLASGOW

DUBLIN

* **Apply**

Chief Engineer:

**A. P. Mason, B.Sc., M.I.C.E., M.I. Struct. E., M.ASCE
THE BRITISH REINFORCED CONCRETE
ENGINEERING CO. LTD., STAFFORD**

SITUATION VACANT. Draughtsman, experienced, required for detailing and designing precast concrete hollow beam flooring. Good salary. Pension scheme. Five-days' week. Apply **GRIFFITHS' FERRO-CONCRETE CO. LTD.**, Great South West Road, Feltham, Middx.

SITUATIONS VACANT. G.K.N. Reinforcements Ltd. have vacancies for experienced reinforced concrete designers and detailers in their offices in London, Birmingham, Glasgow, Southampton and Middlesbrough, and also for their newly-opened office at Wigan. Apply in writing to Chief Engineer, G.K.N. REINFORCEMENTS LTD., G.K.N. House, 22 Kingsway, London, W.C.2.

SITUATIONS VACANT. Reinforced concrete designer-detailers and detailers required by **LEONARD & GRANT** in their South London and Edinburgh offices. Applicants should have three years' minimum experience in position applied for. Good salaries and prospects, luncheon vouchers, etc. Interview by appointment. Telephone: London, MACaulay 6477; Edinburgh, CAL 3807.

SITUATIONS VACANT. Designer-detailers with minimum of three years' experience in reinforced concrete required in our London and Guildford offices. Salary according to qualifications and experience. Pension scheme. Write or telephone for appointment, either Balham 2486 or Guildford 2483. **TERRACON INDUSTRIAL DESIGN ENGINEERS**, 11a Station Parade, Balham High Road, London, S.W.12.

SITUATION VACANT. Consulting structural engineers require fully experienced engineer, both in reinforced concrete and structural steelwork design, detailing and supervision. Must be used to or capable of dealing with clients and have good personality and appearance. Preference will be given to applicant suitable for taking charge of Bristol office. Applications, which must give fullest details, can be sent in strictest confidence to Box 4775, **CONCRETE AND CONSTRUCTIONAL ENGINEERING**, 14 Dartmouth Street, London, S.W.1.

STEEL REINFORCEMENT SPECIALISTS

require the following personnel

SALES MANAGER SALES REPRESENTATIVES

Applicants must be experienced in this field of work, having own connections with contractors, architects, local authorities and consulting engineers. Excellent and lucrative positions for aggressive salesmen and personnel with initiative. Details of experience, etc., to Box 4774, **CONCRETE AND CONSTRUCTIONAL ENGINEERING**, 14 Dartmouth Street, London, S.W.1.

FIRST-CLASS REINFORCED CONCRETE DETAILERS AND CIVIL ENGINEERING DRAUGHTSMEN

required by Consulting Engineers for wide range of work, including bridges. Excellent salaries and prospects. Permanent posts and pension scheme. Write, stating age and full details of experience, to

HARRY BROMPTON & PARTNERS,
7-8 Hobart Place,
Grosvenor Gardens,
London, S.W.1.

WESTERN REGION

of

BRITISH RAILWAYS

require

a senior engineering assistant experienced in the design of prestressed and reinforced concrete bridges, etc. This is a senior post in the Drawing Office and only those experienced in supervising and checking the work of draughtsmen need apply. Salary range £1,175-£1,790.

Interesting work in pleasant conditions with promotion on MERIT.

Superannuation fund

Reduced rates of travel and other concessions.

Five-days' week.

Applications, giving age, qualifications and experience, to

CHIEF CIVIL ENGINEER
BRITISH RAILWAYS
WESTERN REGION
PADDINGTON
LONDON, W.2

CUBITTS

REINFORCED CONCRETE DESIGNERS/DETAILERS

are required for an expansion of structural drawing office.

The work will be interesting and involve the use of precast and prestressed concrete. Experience in these techniques will be an asset, but opportunity will be provided for training those who are interested and have some basic knowledge of reinforced concrete.

Please send full details to:—

Personnel Manager (M.6856),

HOLLAND & HANNEN AND CUBITTS (GREAT BRITAIN) LTD.,

1, Queen Anne's Gate, LONDON, S.W.1.

SITUATION VACANT. Technical representative required by a company specialising in the design and manufacture of precast structural concrete. Contacts with architects and consulting engineers in London and Eastern Counties essential. Car provided. Apply, giving experience and salary required, etc., to Box 4776, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Reinforced concrete designer, designer-drafter and drafter-draughtsman required by consulting engineers, W.1. Interesting work. Good prospects. Laminon vouchers. Five-days' week. Salary £750 to £1,300, according to position and experience. Apply to Box 4777, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATION VACANT. Manager wanted for important new ready-mixed concrete depot in West Riding. Ability to design strength mixes and all-round technological and general experience essential. Excellent prospects in rapidly growing organisation. Applications in strictest confidence to Box 4778, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

STRUCTURAL ENGINEER EXCEPTIONAL OPPORTUNITY

Consulting Civil Engineers, Westminster, require a fully qualified structural engineer with wide experience for position as chief designer in reinforced and prestressed concrete and structural steelwork, including bridges and buildings. Knowledge of modern bridge design essential.

Prospects of partnership interest in firm.

Write in confidence, stating age and full details of experience and qualifications, to Box 4766, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

E. J. COOK & CO. (ENGINEERS) LTD.

Invite
applications from

REINFORCED CONCRETE DESIGNERS AND DESIGNER/DETAILERS

who are at present earning £1,100 to £1,400 per annum, and are prepared to accept responsibility in a position offering interesting and varied experience in structural concrete design and an opportunity to gain experience in prestressed concrete and structural steelwork.

Write or telephone for application form from

54 SOUTH SIDE, CLAPHAM COMMON
LONDON, S.W.4
Telephone: MACaulay 5522

SITUATION VACANT. Civil Engineering Assistant required for progressive office in Stratford-on-Avon, for the design and detailing of reinforced concrete and general civil engineering work. The Company carries out the complete design and construction of a wide variety of industrial and commercial projects throughout the country. Working conditions are exceptionally good, and there are a non-contributory pension and life insurance schemes. Applicants should send details of age, experience and approximate salary required, to R. T. L. ALLEN, W.A., A.M.I.C.E., INDUSTRIAL DEVELOPMENT CONSULTANTS LTD., Industrial House, Stratford-upon-Avon.

SITUATION VACANT. Planning engineer required with experience in contract planning for expanding company based at Hemel Hempstead. Applicants should be familiar with precast and in situ frame construction in addition to general building work. Write, giving age, experience, and present salary, in confidence, to THE CONTRACTS MANAGER, LONDON FERRAS-CONCRETE CO. LTD., Marked Close, Hemel Hempstead, Herts.

SITUATION VACANT. Resident engineer urgently required for reinforced concrete work on large department store and multi-storey garage in Sheffield. Previous site experience, A.M.I.C.E. or A.M.I.Struct.E. essential. Apply CLARKE, NICHOLLS & MARCEL, 27 Westbourne Grove, London, W.3. Telephone: BAYwater 8981.

STRUCTURAL ENGINEERS

Qualified senior designer required to take charge of section working on varied and interesting reinforced concrete projects. High salary, permanent, superannuated employment, with three weeks' leave and luncheon vouchers, offered to keen engineer prepared to accept responsibility. Applications to ALAN MARSHALL & PARTNERS, Consulting Structural Engineers, Smithfield House, Digbeth, Birmingham 5. T. Midland (Birmingham) 0358.

SAMUEL TYZACK & CO. LTD.

urgently require a
REINFORCED CONCRETE DESIGNER-
DETAILER

Interesting work assisting the Floors Department Manager in design, detailing and site supervision of reinforced concrete floors and other structures. This is an expanding department in a progressive medium-size company serving the North of England, and situated close to the pleasant resort of Seaburn.

Graduate structural engineer preferred, minimum qualifications H.N.C., with at least two years' experience. Good salary. Five-days' week. Pension scheme and free life insurance. Apply in writing, with full particulars of experience, to T. W. KIRKBRIDE, B.Sc., A.M.Inst.C.E., SAMUEL TYZACK & Co. Ltd., Fulwell Road, Sunderland, or ring Sunderland 58388 (reverse charge accepted: quote ST0.2).

CONSULTING ENGINEERS BIRMINGHAM

have vacancies for staff in the following categories:

1. Senior engineer experienced in reinforced concrete design and construction. Age 25-35. Salary £1,500-£2,000 per annum.
2. Detailing-draughtsman with minimum five years' experience in reinforced concrete. Age 22-30. Salary £750-£1,250 per annum.

Interesting work, excellent opportunities. Apply for interview by letter or telephone.

ROY BOLSOVER

Consulting Structural Engineer
103 Hagley Road
Edgbaston
BIRMINGHAM 16

Telephone: Edgbaston 5147

SITUATION VACANT. First-class draughtsman required for new consulting engineers' practice. Mainly reinforced concrete but variety of other work. Top salary for right man. Telephone: TATe Gentry 0595. Goudon M. Ross, 10 Rochester Row, Westminster, S.W.1.

**EXPERIENCED
REINFORCED CONCRETE
ENGINEERS, DESIGNERS AND
DETAILERS REQUIRED**

Numerous companies on our registers have vacancies for experienced men in these categories. We are specialists in such technical appointments. NO FEES.

BUSINESS VACANCIES BUREAU LTD.,
33 Victoria Street, London, S.W.1.
Telephone: ABBey 7200

UNIVERSITY OF MELBOURNE

**LECTURER IN CIVIL
ENGINEERING**

Applications are invited for the above-mentioned position. The person appointed will be required to give lectures and assist with tutorial, design and laboratory classes in various civil engineering subjects, principally on the structural side, and he will be expected to engage in research.

The salary range is £1,660 to £2,360 per annum. Initial salary will be determined according to qualifications and experience. Superannuation similar to F.S.S.U. in Great Britain will be provided.

Conditions of appointment and information as to the method of application may be obtained from THE SECRETARY, ASSOCIATION OF UNIVERSITIES OF THE BRITISH COMMONWEALTH (Branch Office), Marlborough House, Pall Mall, London, S.W.1.

Applications close on 20th October, 1961.

SITUATION VACANT. First-class reinforced concrete engineer required to take charge of North Ireland consulting engineers' office. Excellent prospects. Permanent position for right man. Member of Institution of Structural Engineers or Civil Engineers essential. B.Sc. preferred. Write Box 4779, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

FOR SALE.

FOR SALE. Steel plates and sections to size. Also tubes up to 10 in. N/B. E. STEPHENS & SONS LTD., Bath Street, London, E.C.1. Clerkenwell 1731.

FOR SALE. 400 ton Fielding slab press. Box 4773, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

FOR SALE. Mason twin acrlight continuous photocopier. Telephone: CITY 2291.

FOR SALE. Coventry Climax Diesel forklift truck. 5000 lb. capacity. 12 ft. lift. Brand-new solid rubber tyres. 2 speeds forward. 2 speeds reverse. Tilting boom. Hydraulic steering. 48 in. forks. Checked throughout. Stripped to bare metal and re-sprayed in Climax colours of grey and yellow. Excellent condition. Immediately available. Price £1000. SPEED ELECTRICS (Dept. CCE), Church Street, Basford, Nottingham. Tel. 75716.

FOR SALE. Coventry Climax Diesel forklift truck. 6000 lb. capacity. 9 ft. lift. 48 in. forks. New twin pneumatic tyres. New battery. Hydraulic steering. Thoroughly checked and tested throughout. Stripped and repainted. In excellent condition. Immediately available. £1100. SPEED ELECTRICS (Dept. CCE), Church Street, Basford, Nottingham. Tel. 75716.

FOR SALE. Coventry Climax petrol forklift truck. 3500 lb. capacity. 12 ft. lift. New twin-pneumatic tyres. Hydraulic steering. 2 speeds forward. 2 speeds reverse. Tilting boom. Reconditioned engine. Excellent condition throughout. Immediately available. £750. Crane attachment optional extra, £50. SPEED ELECTRICS (Dept. CCE), Church Street, Basford, Nottingham. Tel. 75716.

FOR SALE. Coventry Climax Butane gas-operated forklift truck. 4000 lb. capacity. 12 ft. lift. Solid rubber tyres. Fitted with new mast assembly. Lifting carriage overhauled. New battery. Extremely economical. Satisfactory for interior working. No poisonous fumes. Excellent working condition. Immediately available. Stripped and repainted. Price £695. SPEED ELECTRICS (Dept. CCE), Church Street, Basford, Nottingham. Tel. 75716.

DEVELOPMENT ENGINEER

Applications for the position of Development Engineer are invited from qualified engineers with considerable experience in reinforced and prestressed concrete design.

The successful applicant will be responsible for the development of new designs and existing products. He will also take charge of the Design Office. Experience in precast concrete production would be an advantage but is not essential.

This is a senior position in an expanding department, offering wide scope for an engineer with drive and enthusiasm.

Write in confidence to THE STAFFING OFFICER with full details of qualifications and experience.

THE STANTON IRONWORKS COMPANY LIMITED

P.O. Box No. 3, near Nottingham.

STONE COURT AGGREGATES ★




General View of Plant at Rickmansworth.

ONE OF OUR MODERN CONCRETE AGGREGATES PLANTS

First-Class Washed graded concrete aggregates, and shingles for road dressing, coupled with efficient delivery, are at the service of contractors and Municipal Authorities in London, Berks, Bucks, Herts, and Middlesex Areas.

Our products include Washed Sharp Sand, all sizes of shingles, from 3/16" up to 2", either crushed or natural.

Special Specifications made to order.



STONE COURT BALLAST CO. LTD.

PORTLAND HOUSE, TOTHILL ST., WESTMINSTER, S.W.1

Telephone: Tate Gallery 3456.



THIRD INTERNATIONAL CONGRESS OF THE PRECAST CONCRETE INDUSTRY

Stockholm 1960

CONCRETE PUBLICATIONS LTD.

are distributing the Papers and Reports presented at this Congress
on behalf of the

BRITISH CAST CONCRETE FEDERATION

All the papers and reports presented at this Congress are now available in the English language, in loose-leaf form in substantial binders. The publication is in two editions, one containing the reports and main papers only and the other the reports and main papers plus the reports and supplementary papers.

MAIN PAPERS AND REPORTS are grouped under the headings of Vibration; Shrinkage; Pipes; Precast Concrete for Buildings; Human Relations.

SUPPLEMENTARY PAPERS AND REPORTS on Thin-shell precast concrete; Precast bridge construction; Subways and short-span bridges; Precast flues; Concrete block industry; Test on beam with high strength reinforcement; Electrical curing.

Prices:

Main Papers and Reports.

£3. 3. 0. post free. In Canada and U.S.A. 15 dollars.

Main Papers and Reports with Supplementary Papers and Reports.

£4 4. 0. post free. In Canada and U.S.A. 20 dollars.

CONCRETE PUBLICATIONS LTD.

14 DARTMOUTH STREET, LONDON, S.W.1


"CONCRETE SERIES"

BOOKS ON CONCRETE

For a complete catalogue giving prices in
sterling and dollars, send a postcard to:

CONCRETE PUBLICATIONS, Ltd.

14 Dartmouth St., London, S.W.1



Trent Gravels

10,000 tons per week

Washed & Crushed $1\frac{1}{2}$ in. to $\frac{1}{4}$ in.

We are the leading suppliers of high-class concrete aggregates in the area shown above. Prompt deliveries guaranteed and keen competitive prices quoted. Send for samples and prices.

TRENT GRAVELS LTD

ATTENBOROUGH

NOTTS

Telephone: Nottingham 35 4355

STONE COURT AGGREGATES ★



General View of Plant at Rickmansworth.

ONE OF OUR MODERN CONCRETE AGGREGATES PLANTS

First-Class Washed graded concrete aggregates, and shingles for road dressing, coupled with efficient delivery, are at the service of contractors and Municipal Authorities in London, Berks, Bucks, Herts, and Middlesex Areas.

Our products include Washed Sharp Sand, all sizes of shingles, from 3/16" up to 2", either crushed or natural.


Special Specifications made to order.



STONE COURT BALLAST CO. LTD.
PORTLAND HOUSE, TOTHILL ST., WESTMINSTER, S.W.1

Telephone: Tate Gallery 3456.





*Specialists in Reinforced Concrete Design
and Suppliers of Reinforcement*

THE BRITISH REINFORCED CONCRETE ENGINEERING CO. LTD., STAFFORD

London, Birmingham, Bristol, Chelmsford, Leeds, Leicester, Liverpool, Manchester, Newcastle, Cardiff,
Glasgow, Dublin, Belfast, Bulawayo, Calcutta, Johannesburg, Singapore, Vancouver
Export Sales: 54 Grosvenor Street, London W.1

